MICROCOPY RESOLUTION TEST CHART

NATIONAL BUREAU OF STANDARDS 1963 A

AD-A180 322

The Pennsylvania State University

The Graduate School

Department of Civil Engineering

SFTYCHEF: A Consultative, Diagnostic Expert System
for Trench Excavation Safety Analysis
on Light Commercial Construction Projects

Contract N00228-85-G-3278

A Report in

Civil Engineering

by

Thomas C. Nicholas

Submitted in Partial Fulfillment
of the Requirements
for the Degree of

Master of Engineering

DTIC
ELECTE
APR 2 8 1987
A

Thomas C. Nicholas, LT, CEC, USN

DISCLAIMER NOTICE

THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.

We approve the report of Thomas C. Nicholas

_3/23/87_
Date

[signature] J. H. Willenbrock,
Professor of Civil
Engineering, Bernard
Hankin Professor of
Residential Building
Construction, Report
Advisor

_3/3-/87_
Date

[signature] M. S. Bronzini, Professor
of Civil Engineering,
Head of the Department of
Civil Engineering

Contract N00228-85-G-3278

ABSTRACT

The development of a prototype knowledge-based expert system to assist safety analyses of short term, trench excavations on light commercial construction projects is presented.

Background information of trench excavation hazards, OSHA safety compliance regulations, in-the-field soils analysis techniques, timber shoring design, and expert system development is introduced. Detailed discussion of the design and construction of a knowledge base for the safety analyses of short term trench excavations is included along with the methods involved in loading the knowledge base onto an expert system shell.

TABLE OF CONTENTS

LIST OF FIGURES

CHAPTER 1

INTRODUCTION

Introduction and Problem Statement

The Need for Trench Safety Research

In September of 1985, the Occupational Safety and Health
Administration commenced a nationwide "special emphasis"
inspection program aimed at combatting alarming fatality
rates in construction trench excavations. Within one year,
1,764 trench inspections resulted in over 2,800 citations for
safety violations (58). Unfortunately, it is questionable
whether this statistic is a trend indicator or merely the
reflection of common practice viewed closely for the first
time. Each year hundreds of construction workers are injured
or killed on the jobsite due to trench wall cave-ins, slides
of spoil bank material into the trench, drownings in the
trench, and other mishaps which are the result of a lack of
proper consideration for safe construction practices.
Although the problem is not a new one, there is as yet no
obvious method that will guarantee a safe trench. In
addition, the expertise needed to provide case by case
analyses of soil type, lateral earth pressures, and retaining
structure design is often too expensive or unavailable to the
small contractor. Often the only safety considerations

provided are the result of concerned and knowledgeable, though technically inferior, field supervisors.

Components of a Safe Trench Excavation

The construction of a safe trench stems from an in-depth consideration of four factors:

1. A soils analysis must be made and supplemented with knowledge of site conditions. Traditionally, the goal of this analysis was to determine cohesion, angles of internal friction, depth of the water table, layering of differing soils, and other factors so that lateral earth pressure equations and diagrams could be developed and retaining structures designed based upon the results. The time and cost of such studies, however, have made them unattractive to the small contractor involved in short-term operations.

2. An adequate method of trench wall stabilization must be developed. Three main techniques exist to perform this task. The wall can be removed by sloping of the trench banks, the wall can be actively restrained by applying lateral pressure via timber frame or hydraulic shores, or the wall stabilization can be neglected and the workers

2

protected by using protective coverings such as trench boxes.

3. The existence of any job dependent construction activities which will influence trench stability must be considered. Such practices include: the operation of heavy equipment; drilling and blasting adjacent to the trench excavation; excessive pumping or dewatering; and excavating adjacent to existing foundations.

4. Attention must be given to all the miscellaneous safety features which job conditions may dictate. Respiratory protection, dust reduction, noise protection, ramp, ladder and walkway construction, and hazard awareness marking are but a few of the features that may be required.

Applicability for Solution via Expert System

An adequate solution to this problem cannot be generalized for all trenches on all construction projects. The problem has certain characteristics, however, which will allow an encompassing solution using a very new and interesting technology. The expertise exists and is available to provide a proper safety analysis in all situations. As various safety records attest, the solutions developed by professionals have been proven to be better than

3

those of experienced field supervisors. The solution for most trench excavation situations is not lengthy. An expert, given the proper information, could provide the necessary solution in a matter of hours. As was previously mentioned however, the problem is often ill-structured. Seldom do two jobs have identical conditions or requirements. In addition, the expertise is often derived from subjective knowledge. Solution of this problem has a very high payoff; the number of jobsite fatalities can be reduced. These characteristics make the problem ideal for the application of expert system technology.

Background: Expert Systems

Definition of an Expert System

"Expert System" is not a very familiar term for many civil engineers. To those who have done casual reading in artificial intelligence, it may summon images of futuristic, computerized managers, capable of decision making and supervision of a variety of tasks. Although such conceptualization can be defended, the reality of expert systems is more practical.

Fundamentally, an expert system is a computer system consisting of a central processing unit, a terminal, a screen, a printer, and a software package which embodies the knowledge of an expert to assist a user in making expert level decisions. The expert knowledge consists of a

4

collection of facts held in a database and a set of rules which relate these facts. Figure 1.1 presents an illustration of one such rule.

As the user inputs information at the terminal about the problem, the computer records the information, selects appropriate facts from the database, validates certain conditions, and then selects and applies the rules which the conditions satisfy. In this manner, the system proceeds or chains through its rules until final actions or a solution is reached. Chapter 2 will provide an elaboration on the history of, the application, and the design of expert systems.

Sources of Knowledge for Trench Safety

The power of an expert system is wholly dependent upon the quality of the knowledge encoded in the database. For the problem at hand, or domain of application, the knowledge has been drawn from a number of sources.

In order to provide guidance and legal standards for safe trench excavation operation, OSHA developed the Code of Federal Regulations, 29 CFR 1926/1910, Subpart P (61), which deals with construction safety for excavations, trenching, and shoring. This publication is a segment of the Code of Federal Regulations (CFR) 1926/1910 (61) which provides safety standards for the construction industry. OSHA 1926

RULE NUMBER: 137

IF:

    (1)   The class of soil is type III

and (2)   The depth of the trench is 10-15 feet or 15-20

                feet or 20+ feet

THEN:

    (1)   [We] IS GIVEN THE VALUE 60

and (2)   [SLOPE] IS GIVEN THE VALUE "(1 1/2 : 1)"

NOTE: If there is any indication of general or local

        instability, slopes shall be cut back to a slope which

        is at least 1/4 Hor : 1 Vert. flatter than the stable

        slope.

REFERENCE: NBS Building Science Series 127, Recommended

           Technical Provisions for Construction Practice in

           Shoring and Sloping of Trenches and Excavations,

           Table 3.3, Minimum Acceptable Stability

           Requirements for Matrix System.

           Figure 1.1   Sample Expert System Rule

was last revised in 1979. Although this document is the law, a number of other organizations have published supplementary standards and directives. EM 385-1-1, Section 23 (60), is the document utilized on many military and government jobsites. Technical research done by the National Bureau of Standards so that OSHA 1926 might be updated led to four very useful publications. NBS, BSS 121, Soil Classification for Construction Practice in Shallow Trenching (56); NBS, BSS 122, A Study of Lumber Used for Bracing Trenches in the United States (57); NBS, BSS 127, Recommended Provisions for Construction Practice in Shoring and Sloping of Trenches and Excavations (58); and NBS/NIOSH, Development of Draft Construction Safety Standards for Excavations (59) contain very useful expertise. It is from these documents that a contractor would draw the information necessary to construct and operate a safe trench. This information has been used to compile a knowledge base to be utilized by the expert system.

Objectives

The following five objectives provide the framework for this research effort.

1. The collection and structuring of the body of knowledge utilized in the domain of safety in trench excavations.

2. An in-depth investigation of applicable expert system domains from the realm of civil engineering and construction.

3. A presentation of basic expert system design and construction methods to provide a starting point for other researchers in construction.

4. The development of a prototype expert system to provide consultative advice to contractors involved in trench excavation operations on light commercial construction projects.

5. Identification of the areas of expert system research, in construction, which need to be explored in greater detail.

Research Methodology

The principal methods utilized to accomplish the five objectives were literature search, formal classroom study, non-structured interviews with experts in expert system design, and hands-on application of expert system software.

Remarks on Literature Search

Objectives 1, 2, and 3 were covered primarily via literature search but several remarks need to be made.

Although knowledge can be collected from various sources of varying reliability, its representation or structure is vital to the success of expert system implementation. Knowledge representation is not a concept to be taken lightly and the techniques utilized cannot be learned from a literature search. The techniques available and those attempted will be discussed in Chapters 3 and 4. An explanation of applicable expert system domains and a presentation of design skills and methods can only be made after hours of time have been spent on the computer attempting to implement a variety of ideas. There is a mistaken concept prevalent among many engineers that expert system development requires extensive domain knowledge and enough computer background to understand the written literature. Any research effort in the area of expert systems requires considerably more computer science knowledge than an engineer typically acquires in undergraduate or graduate studies. Expert Systems are among the state of the art in computer systems in artificial intelligence. This paper could not possibly detail the computer background mandated by such research. Let it be sufficient to say that an extensive portion of the research methodology must be devoted to learning skills which are often outside the researcher's area of expertise.

Method of Prototype Development

The development of the prototype, SFTYCHEF, was accomplished via interaction with EXSYS, an expert system

9

shell produced by EXSYS Incorporated of Albuquerque, New Mexico. The particulars of expert system shells and the techniques utilized in loading such a shell are contained in Chapters 4 and 5.

Scope and Limitations

It is important at the outset of this report to identify the boundaries within which this research was conducted and to provide overall guidance concerning the use of the developed prototype.

Limitations of the Domain

The domain of application is the safety analysis of trench exc.   'ions on light commercial construction projects. These trenches ᵃ ᵣₑ typically limited to those less than 20 feet deep and op   for a period of 24 hours or less. These parameters of 20 feet of depth and 24 hours of open time are critical factors in the following analysis. Dr. Felix Yokel (58) has determined that trenches of a greater depth and open for a longer time exhibit significantly different stability characteristics. The stabilization methods investigated and included in the prototype are timber shoring and bank sloping. The system does not include any knowledge of trench jacks, hydraulic shores, trench boxes, sheet piling, thermal stabilization or other stabilization techniques. The addition of any or all of these to SFTYCHEF would not be

technically difficult and will be discussed in Chapter 5.
The reason for their exclusion is that each method by itself
is worthy of its own research study and the amount of
knowledge to be covered greatly exceeds the time constraints
of this research and the memory and processing capabilities
of the expert system shell.

Basis for Soils Analysis

The determination of soil type and lateral earth
pressures are based on the Matrix Classification System
developed by the National Bureau of Standards (56).

Basis for Timber Shoring Design

The timber shoring design recommendations are based on
OSHA 1926, Subpart P, Table P-2 (61). Although there are
questions regarding the accuracy of this table, it remains
the legal standard to which contractors are held, thus it was
not modified. A discussion of potential errors and suggested
revisions are presented in Chapter 5.

Expert Interaction

The development of an expert system typically requires
several months of interaction between the system designer, or
knowledge engineer, and selected experts. Such interaction
mandates that an expert or experts in the domain of
application be dedicated to system development. Attempts
were made to involve experts from OSHA's regional office in

Philadelphia, OSHA's field office in Harrisburg, the Naval
Facilities Engineering Command in Washington, D.C., and the
Army Corps of Engineers Construction Engineering Research
Laboratory in Champagne-Urbana, Illinois. Although some were
more cordial than others, no one was willing to dedicate the
time of an expert to such research. Therefore, the majority
of the knowledge included in this prototype is textual. It
should be noted that the full-time involvement of an expert
is one of the hidden costs of system development. Rarely, if
ever, can a valid system be built without continuous expert
interaction. A weekly meeting or spot interviews will not
suffice. SFTYCHEF, though accurate and justifiable, could
have been improved greatly if there had been more active
expert interaction.

Use of the System

Emphasis needs to be placed on the words "consultative"
and "prototype" in the system description. SFTYCHEF was
designed to assist decision making and to educate its user.
It will not replace an expert nor will it serve as a
professional engineer. The system is prototypical in that
much work remains to be done before such a system can be
applied by construction project personnel.

At this point, the limitations imposed may seem to
greatly restrict the system's performance. The remainder of
this paper should clarify the need for such restrictions and
provide guidance for their removal. Chapter 2 will highlight

the use of expert systems in construction and will provide
introductory instruction concerning system development.
Chapter 3 will look closely into the problem of trench safety
analysis and will concentrate on soils analysis, timber
shoring design, slope stabilization, construction site
practices, and miscellaneous safety features. Chapter 4 will
then detail how this information was represented and encoded
to create SFTYCHEF. The final two chapters will give
specific guidance to users and future researchers.

CHAPTER 2

AN OVERVIEW OF EXPERT SYSTEMS

FOR

CONSTRUCTION ENGINEERING AND MANAGEMENT

Introduction to Expert Systems

Definition

The widespread applicability of microcomputers to the
construction industry has prompted extensive software
development in a variety of areas. Design, material
procurement, finance, scheduling, and quality control, to
name a few, are widely supported by software packages and
their associated hardware. Recently, a new type of computer
system has gained prominence in construction, as well as in
other fields of civil engineering. These systems have their
roots in artificial intelligence and are commonly known as
expert systems.

As was mentioned in Chapter 1, an expert system is a
computer system which utilizes expert knowledge to assist its
operator in making expert level decisions. In order to build
on what has already been discussed, let us look at a very
simple example of how facts and rules interrelate in a
decision making situation. Consider an engineer trying to
determine the suitability of using a compacted soil base for

supporting a concrete slab. The system database may contain
information on soil types, compaction techniques, suitability
for foundations, and various standard specifications. It
would also include rules, such as, "IF the compaction
achieved exceeds 95% of the optimum at a specified moisture
content, THEN the soil is suitable for slab placement." The
user would volunteer any information he has about the actual
conditions on the project under consideration and the system
would prompt him for further information, and perhaps
recommend the tests and methods to be used if additional
information is necessary. As the information is acquired,
the system selects the applicable rules and fires[1] them to
make the appropriate decision.

Conceptually, the technique is not particularly
abstract. Its use applies to any problem which requires
expertise that is not readily available. Although at this
stage, the development and implementation may seem easy,
further exploration quickly reveals that this is not so.

A more specific definition of what characteristics
comprise an expert system depends greatly upon the author who
is providing the definition. All sources, however, seem
united on identifying the following seven characteristics.

1. EXPERTISE - The most important goal in expert system
work is to attain the high level of performance that a human

---

[1]The validation of the truth of a rule is known as FIRING the rule.

15

expert achieves in some task (26). This inherently implies that such a system must **know** what the expert knows. It also means that the system should behave like an expert, producing high quality results in minimal time, employing skills developed through years of experience, and utilizing well founded **hunches** to quickly eliminate false conclusions. High quality results are simply results that are right, but as can easily be imagined, problems unfold quickly when right and wrong answers are not known or when multiple right answers exist. The utilization of hunches to perform block elimination is referred to as inferential leaping. An expert, when confronted with a problem, does not perform an algorithmic search and test of every possible solution, but instead narrows the field of solutions in large blocks based on his past experience. Such ability is often cited as the difference between an expert and a skilled technician.

2. SYMBOL MANIPULATION - An expert system represents knowledge symbolically. The matching or relational linking of these symbols to derive new inferences is called symbol manipulation.

3. GENERAL PROBLEM SOLVING ABILITY IN A DOMAIN - An expert system must possess the ability to reason from first principles. For example, if the system spoken of earlier was prompted with the query "why ?" following its inference on the suitability to pour the concrete slab, it should be able

16

to provide the elementary knowledge of soil type, testing procedures, and reasoning used to support the validity of 95% compaction implying suitability. It is worth noting that systems which provide expert answers in series response to pre-asked questions are not difficult to design and are not expert systems.

4. COMPLEXITY / DIFFICULTY - Perhaps relating more to the definition of expert, if the domain over which the system is defined is not somewhat complex, then true expertise does not exist and the system is not expert.

5. REFORMULATION - A distinguishing characteristic of an expert is the ability to restructure a problem in a form which has been dealt with previously. This ability is termed reformulation.

6. REASONING ABOUT SELF - An expert system contains knowledge about what it knows (meta-knowledge). It must also have the capability to remember/reconstruct the paths of inference followed while reaching a decision.

7. TASK - At this point in time, expert systems are highly task oriented. They are not capable of abstract reasoning. The system exists to solve a particular set of problems in a well defined domain.

Although these seven elements are present in varying

degrees in most expert systems, the technological difficulties involved have thus far precluded any well publicized system from embodying all seven elements to their fullest extent. Many other characteristics of these systems, such as common sense capabilities, reasoning by analogy, and learning from experience (i.e. becoming more expert) could be added to the list of seven but their necessity in defining an expert system is not well justified.

Composition

To this point, the function of an expert system has been briefly defined and the performance characteristics of an expert system have been described. The specific components of an expert system have not yet been revealed. When one looks closely at the composition of an expert system, one finds:

1. KNOWLEDGE CONSISTING OF DOMAIN RELATED FACTS - This knowledge is called **declarative** knowledge. It establishes the existence of facts within the database upon which the system must rely.

2. KNOWLEDGE CONSISTING OF DOMAIN RELATED RULES - This knowledge is called **procedural** knowledge. It relates the facts in an IF-THEN format so that inferences can be drawn. Declarative knowledge and procedural knowledge are both a combination of **deep** knowledge, that based upon scientific

fact, and **surface** knowledge, that based upon personal experience. Surface knowledge is commonly known as heuristic knowledge or rules of thumb.

3. <u>AN INTERPRETER THAT APPLIES THE RULES</u> - The system contains a mechanism that selects the applicable rules from the knowledge base. The selection is initially based on user input.

4. <u>AN ORDERING MECHANISM</u> - After the interpreter has selected the pertinent rules, the ordering mechanism establishes the flow pattern to be followed. This ordering is critical to the derivation of valid and justifiable conclusions. The interpreter and the ordering mechanism are often termed the "**inference engine**" of the system.

5. <u>CONSISTENCY ENFORCER</u> - A consistency enforcer insures that inferences are drawn in a consistent manner and that procedures do not change with the addition or deletion of knowledge from the database.

6. <u>JUSTIFIER</u> - The user of the system often considers the justifier to be the most valuable component. It retraces the paths of inference in an effort to explain its conclusion to the user. A system which produces obvious results or surprising results without justification is neither expert nor valuable.

Utilization of Expert Systems
in the Construction Industry

Proper Domains of Application

When considering the application of an expert system to a particular problem domain, it is necessary to insure that experts exist in that domain. Perhaps this seems obvious but it is important to note that expert systems can only be utilized when a high level of expertise exists. This is unfortunate. There are many fields of science and technology which cannot benefit from such a system because the level of expertise is too limited.

The domain of application must be one in which experts are provably better than amateurs so that expert performance can be verified. The problem to be solved should be solvable in a time span of several minutes to several hours. The problem should be ill-structured and the solution somewhat cognitive. A problem solvable by rigorous application of mathematical algorithms is inappropriate.

The development of an expert system must also have a high payoff. The development of a major system takes years and often millions of dollars. The results obtained must justify the expenditures.

Early Applications

With these thoughts in mind, B.G. Buchanan developed a

20

pioneer system in 1965 known as DENDRAL (6). DENDRAL defined

the fundamental concepts of expert systems by utilizing a

database of expert, heuristic knowledge to infer molecular

structure from mass spectrographic data. The system, though

later modified, has proven very reliable.

CASNET (65), developed in the early 1970's, assists

doctors in their diagnosis and treatment of glaucoma

patients. It advanced expert system technology by

successfully encoding probabilistic rules within its

knowledge base to provide confidence factors for the answers

that were generated.

Perhaps the most heralded of the early systems is

MYCIN (50). Developed in the mid-1970's, it gives

consultative advice on diagnosis and therapy of infectious,

bacteriological, diseases. Two of its offspring, EMYCIN

(63), and TEIRESIAS (14), have also been highly acclaimed.

EMYCIN is an expert system that assists expert system

development, and TEIRESIAS is an expert system that can

acquire, modify, and format new knowledge to update MYCIN.

Since these early systems, the realm of applications has

exploded and includes systems that teach, monitor, repair,

design, plan, predict, diagnose, interpret, debug, and

control. Appendix 1 provides a partial listing of the

systems developed to this point along with their

applications.

Constructic~ Applications

Many of the system applications relate closely to

problems experienced in the construction industry. The use of expert systems to handle such problems is still in its infancy however, and most construction systems are still prototypes.

CRITIC/ESRAM. The U.S. Army Corps of Engineers builds and maintains thousands of miles of railroad track in this country. They employ numerous engineers who serve as quality control inspectors in this area and a major problem they face is inspecting and detecting deteriorating subbases and recommending feasible solutions. Since there is a shortage of experienced inspectors, the Corps wanted an expert system to act as a consultant for the field inspector. The system, developed by the Construction Engineering Research Laboratory, CERL, which is called CRITIC/ESRAM (32), allows the inspector to input field conditions into the system and obtain a series of analyses and courses of action. The system not only alleviates much of the inexperience among inspectors but also provides continuous, interactive tutoring of the inspector, thereby increasing his expertise.

CRITIC is Pascal driven and operates under the UCSD P-System DOS^2 package on a variety of microcomputers. Its strongest points are its excellent explanatory capabilities and user friendliness. The system first explains its command options to the user and details the appropriate time to issue each particular response. The system then leads the user

^{2}University of California, San Diego P-System Disk Operating System.

22

through a consultation. It asks the user to provide
information on moisture content, pumping, ditches,
settlement, and other pertinent information, explaining each
request if necessary. When the system has gained enough
knowledge to output a recommendation, it does so, along with
displaying all rules selected and tested and the effect of
each on the solution. CRITIC is a functioning expert system
which, though not large in scale, provides needed assistance
to field inspectors.

AUGERPILE. The majority of main-frame expert systems
developed have cost a considerable amount of money. The
result has often been a very powerful improvement of a system
which could have been implemented on a microcomputer.
Occasionally though, the system developed is not cost
effective. Nitin S. Pandit and D. Sriram of Carnegie-Mellon
University (31) have approached this problem by taking
potential main-frame systems and implementing them first on a
microcomputer to establish their potential worth before
committing to large expenditures. One such system is
AUGERPILE (31).

AUGERPILE is an expert system designed to aid in the
field inspection of augered, cast-in-place, concrete pile
installations. It uses an expert system shell known as
INSIGHT (30). Such a shell is essentially an expert system
with the knowledge base removed. Shells will be discussed in
greater detail later in this chapter.

Augered, cast-in-place piles are a specialized form of

23

deep foundation. They are friction piles, transferring a
load from a superstructure to the soil via frictional
resistance between the soil and the pile surface. They are
best suited to areas where the soil is too soft to use more
conventional methods. These piles can support loads of up to
100 tons.

The installation of these piles is not complex. Usually
the necessary resources are an adapted drilling rig, one
operator, a foreman, an inspector, and the materials. The
operator augers a hole without excavation using a hollow
auger. While raising the auger, grout (cement, aggregate,
fluidifiers, additives, and water) is pumped through the
hollow auger stem. The problem most often encountered is
necking. Necking is the bulging or constriction of the
diameter of the pile in areas where soft, loose, water
bearing soil exists or where man-made fill leaves unexpected
voids.

The inspection of this operation is difficult because
observations can only be made from the surface. Load tests
and pullout tests are elaborate and expensive. Acoustical
monitoring and geophysical methods provide data that is too
uncertain to make a quality control analysis. The inspection
is a highly judgement prone process. Results obtained by an
inexperienced inspector or contractor are unreliable.

AUGERPILE serves as a consultant which prompts the
inspector to view five areas of the installation in great
detail. Based upon the inspector's description of the

operation, a determination of successful placement is made.

A sample rule from AUGERPILE, shown in Figure 2.1, illustrates the user friendliness of systems built with shells. Figure 2.2 is a comparable rule written in FRANZ LISP for another system. FRANZ LISP is an adaptation of LISP (LISt Programming) which is used extensively at the Massachusetts Institute of Technology (31).

****

```
RULE:   Final Judgement

    IF:   equipment was OK

        AND:   starting conditions were OK

        AND:   grout mix was OK

        AND:   installation so far was OK

        AND:   steel installation was OK

  THEN:   Augerpile installation passed

        AND:   Display pass

  ELSE:   Augerpile installation failed

        AND:   Display fail
```

FIGURE 2.1 AUGERPILE RULE USING INSIGHT EXPERT SYSTEM

SHELL   (31, p. 20)

****

```
*****************************************************************

        RULE 3:  TRIANGULAR LOAD


              (if(?load is triangular)

                    then

                          (list 'load'*

                                (list 'rloc' - 'lloc)

                                    '*'0.5))


        FIGURE 2.2    SIMILAR RULE IN FRANZ LISP

                      (31, p. 35)



*****************************************************************
```

An Expert System for Shallow Trench Excavation. Recently,
researchers at Carnegie-Mellon completed work on a report
which parallels the writer's work in many respects.   In April
of 1986, G.M. Konkoly, D.R. Rehak, and P.P. Christiano (10)
released a technical report summarizing work on a prototype
expert system for shallow trench excavation.

The research effort was constructed around two main
objectives. First, it was hoped that a Knowledge Base Expert
System (KBES) could be developed which would assist
construction foremen in applying the new soil analysis and
trench shoring standards developed by the National Bureau of

Standards (56). The approach taken by NBS to soil classification led to the development of two new methods, the Matrix Classification System and the Simplified Method (56). Both of these methods provide the construction foreman with a systematic, non-laboratory procedure for classifying soil types. This classification can then be used to identify the proper design for a timber frame shoring system.

The report also addressed two prominent issues in current expert system literature, knowledge acquisition, and the selection of an appropriate KBES environment. G.M. Konkoly was fortunate enough to work directly with Dr. F. Yokel (58) at NBS. Dr. Yokel headed the study to revise the OSHA trench shoring standards. The period of interaction is well documented in the report and it provides valuable insight into some of the difficult aspects of knowledge acquisition. Konkoly then did a comparative analysis of the compatibility of the trench shoring domain with OPS-5 (23), INSIGHT (30), and PERSONAL CONSULTANT (45), three commercially available expert system shells. The research effort led to the use of PERSONAL CONSULTANT for her work.

The outcome of the research was a prototype expert system which utilizes both the Matrix Classification System and the Simplified Method to perform an "in-the-field" soil analysis. The report proposes expansion of the system to incorporate timber frame shoring design, hydraulic shoring usage, trench jacking, and the installation of trench boxes. In depth background information on the theory of soils,

trenches, and braced excavations is provided in the report.
The difficulties inherent in the design of timber frame
shoring are thoroughly discussed. The work at CMU provided
essential background to the research in this report. The
Matrix Classification System forms an integral part of
SFTYCHEF, a prototype expert system introduced in Chapter 4
of this report.

The examination of systems to this point was approached
from a problem domain point of view so that an appreciation
could be gained for the types of work expert system can do.
The section below will examine how such systems are built.

Building An Expert System

D.A. Waterman (26), noted co-author of the text.
Building Expert Systems has stated, "Choices regarding the
desired initial capabilities determine what knowledge to
acquire first and how to engineer it for use."

Problem Definition

It was previously mentioned that expert systems are task
oriented, built to solve a particular problem. The initial
step in building an expert system is to define the problem.
Current methods of solution should be studied. A very close
look at applicable expert system domains must be made. Are
there experts in the field? Are the experts provably better
than amateurs? What is the duration of a typical problem

solution? Is the problem ill-structured and somewhat
cognitive? Are inferences drawn from subjective knowledge?
Does the solution via expert system offer a high payoff? A
well focused problem leads to a well focused solution.
Expert systems are not capable of creative thinking. If data
has been left out of the knowledge base, it can't be used to
draw inferences.

Knowledge Acquisition

Once the problem has been defined as a problem worthy of
expert system technology, a knowledge engineer commences the
process of knowledge acquisition, representation, and
coordination. A knowledge engineer is an expert at the
techniques used to gather information and to represent it in
an implementable code.

The knowledge engineer begins by familiarizing himself
with the problem. He locates the sources of expertise, such
as books and people, and visits those most familiar with the
problem. During this period of familiarization, he
characterizes the problem solution as either: (1)
interpretation, (2) diagnosis, (3) monitoring, (4)
prediction, (5) planning, or (6) design. He then meets with
the expert or experts who will assist him throughout the
project in order to review the parameters established during
the problem definition phase.

The knowledge engineer may spend several months in
meetings with the expert(s). During this time, the engineer

29

is attempting to acquire the facts that the expert knows
about the problem solution and what basic solution strategies
the expert utilizes. These facts and strategies are the
foundation for the knowledge base. The knowledge acquired at
this point also forms the basis for the system's explanatory
capabilities.

Knowledge Representation and Coordination

As the knowledge engineer collects information, he
structures it, or represents it in a manner that makes the
relationships between data items more apparent. Knowledge
representation is a field of study in itself but an overview
is essential to a basic understanding of the design process.

One technique used to represent knowledge is STATE-SPACE
representation. Each data item is assigned a given location
at a particular time, much like the pieces on a chess board
during a game. Their interrelationships are determined by
their locations at a given time. A more common
representation scheme is SEMANTIC NETS. Semantic nets group
similar data into object classes and display relationships
between these classes as linkages. (See Figure 2.3)

LOGIC REPRESENTATION is yet another way to represent
facts and their relationships. Logic representation includes
first order predicate calculus, frame representation, entity-
relationship diagramming, network diagramming, and
hierarchical diagramming.

Predicate calculus uses logic statements to represent
facts and axioms in predicate form. Inferences can be drawn
from the two. For example, let us represent the fact that
all CAT 651B's are scrapers. In predicate calculus it would
be stated as follows: CAT_651B(x)--->SCRAPER(x). An axiom
such as "All scrapers require maintenance every 40 hours" may
look like x.SCRAPER(x)--->40_MAINT(x). This expression is
read, "For all x, such that x is a scraper, x requires 40

****

FIGURE 2.3:   EXAMPLE OF SEMANTIC NET REPRESENTATION

****

hour maintenance." From these two predicate representations,
the system could derive the inference CAT_651B(x)--->
40_MAINT(x). This is, of course, a very simple example but
it illustrates one way that facts are represented so that a
new fact can be inferred. For an in-depth treatment of

31

entity-relationship diagramming, network diagramming, or hierarchical diagramming, the interested reader is referred to *Principles of Database Systems* by J.D. Ullman (55) and *An Introduction to Database Systems* by C.J. Date (13).

After the knowledge engineer has represented the facts and their interrelationships, he must formulate the rules which connect various facts and axioms in every situation to be considered. Figure 2.4 illustrates the knowledge acquisition, representation, and coordination tasks as seen by Waterman (26).

The evolution of expert system technology has suggested the possibility of performing this entire process without using a knowledge engineer. Methods of automated knowledge acquisition are shown in Figure 2.5. One such possibility uses an intelligent editing program that converses directly with the expert and collects, represents, and coordinates knowledge, and implements it for use. Another method uses a program which takes data from case histories as input and formulates the knowledge base. A third technique would be to use text understanding software to gather data directly from textbooks.

All knowledge in its final form must undergo extensive testing to assure the validity of all inferences drawn. This critical process is often long, repetitive, and difficult. Problems arise from many sources. There is often a discrepancy between the way an expert says he solves a problem and the way he actually solves it. In such a

****

IDENTIFICATION   CONCEPTUALIZATION   FORMALIZATION

| Identify
Problem
Characteristics | → | Find Concepts
to Represent
Knowledge | → | Design Structure
to Organize
Knowledge |

IMPLEMENTATION   VALIDATION

| Formulate Rules
to Embody
Knowledge | → | Validate Rules
That Organize
Knowledge |

FIGURE 2.4   STAGES OF KNOWLEDGE ACQUISITION

(26, p. 139)

****

33

****

```
EXPERT ──────────▶ KNOWLEDGE ENGINEER              EXPERT SYSTEM
                              │              ┌─────────────────────────┐
                              │              │ Inference Engine        │
                              └─────────────▶│                         │
                                             │ Knowledge Base          │
                                             └─────────────────────────┘


EXPERT ──────────▶ INTELLIGENT EDITING             EXPERT SYSTEM
                   PROGRAM      │              ┌─────────────────────────┐
                                │              │ Inference Engine        │
                                └─────────────▶│                         │
                                               │ Knowledge Base          │
                                               └─────────────────────────┘


EXPERT ──────────▶ INDUCTION PROGRAM               EXPERT SYSTEM
                              │              ┌─────────────────────────┐
                              │              │ Inference Engine        │
                              └─────────────▶│                         │
                                             │ Knowledge Base          │
                                             └─────────────────────────┘


TEXT ────────────▶ TEXT UNDERSTANDING              EXPERT SYSTEM
                   PROGRAM      │              ┌─────────────────────────┐
                                │              │ Inference Engine        │
                                └─────────────▶│                         │
                                               │ Knowledge Base          │
                                               └─────────────────────────┘
```

FIGURE 2.5   METHODS OF AUTOMATED KNOWLEDGE ACQUISITION

(26, pp. 130-132)

****

mismatch, the program logic must be changed to match the expert's technique, not his explanation. In some instances, experts are not able to verbalize their expertise. A third difficulty occurs during system validation when an obvious wrong answer is provided and the system must be traced. At this stage of development, a system has no self tracing capability so a hand trace must by made of all possible logic paths to identify the error. Such a process is tedious.

Inference Mechanisms

Once the knowledge base has been validated, an inference mechanism must be developed. Recall that the inference mechanism consists of an interpreter which selects the rules to be fired, and an ordering mechanism that decides in what order the rules are to be fired. According to Fox (24), the four primary inference mechanisms in use today are:

1. HEURISTIC SEARCH

2. ANALYTICAL TOOLS (Linear Programming, Dynamic Programming, Queuing Theory)

3. CONSTRAINT DIRECTED REASONING

4. HIERARCHICAL REASONING

All of these mechanisms share common characteristics. Each utilizes some sort of chaining, either forward or backward, to move through the rules. A simple example may help explain the difference between forward and backward

chaining.

Forward Chaining System

When forward chaining, the system takes the input and searches the knowledge base for a matching predicate. It selects those rules whose predicates match, fires them, and looks for new predicates to match the newly validated objects. It continues to do this until a solution is reached.

USER INPUT: Is the subbase suitable for slab placement?

SYSTEM RESPONSE: What is the compacted elevation, in

feet?

USER INPUT: 1206

SYSTEM (RULE 1): If grade elevation = specified elevation, then check compaction.

SYSTEM RESPONSE: What is the compacted density (%) ?

USER INPUT: 95

SYSTEM (RULE 43): If compaction >= 95, then subbase is suitable for slab placement.

SYSTEM RESPONSE: The subbase is suitable for slab placement because the compacted elevation equals the specified elevation and the compacted density is >= 95% .

As can be seen, forward chaining essentially is "data driven", the next question being determined by the response to past questions or the current state of the database.

Backward Chaining System

In backward chaining, the system commences its search from the goal state, proceeding backwards through the rules, determining what conditions must be satisfied in order to validate the solution. Only questions relevant to the determination of the truth or falsity of the conditions concerned will be asked.

USER INPUT: Is the subbase suitable for slab placement?

SYSTEM (RULE 43): The subbase is suitable for slab placement, if compaction is >= 95% .

SYSTEM (RULE 1): Compaction is checked if the elevation is equal to the specified elevation.

SYSTEM RESPONSE: What is the compacted elevation, in feet?

USER INPUT: 1206

SYSTEM RESPONSE: What is the compacted density (%) ?

USER INPUT: 95

SYSTEM RESPONSE: Since the compacted elevation matched the specified elevation and the compacted density exceeded 95%, the subbase is ready for slab placement.

An important thing to note is the reversal of the rule

structure in backward chaining. IF-THEN rules are actually utilized as THEN, IF rules.

An inference mechanism must contain a consistency enforcer. The consistency enforcer ensures that rules added to update the rule base are consistent with one another. One can see the potential difficulty in having two rules with the same antecedent and opposing consequents.

Programming Skills

An underlying skill of the knowledge engineer which has not yet been addressed is that of programming. The engineer may not have to write the code himself, but must be intimately familiar with the language to be used and its strengths and weaknesses. The languages of expert systems are often as unique as the problems of application. It is not uncommon for a system designer to modify a language to fit his particular needs and then to build his own compiler. The languages which are currently best suited for expert systems are PROLOG (PROgramming in LOGic) (11) and LISP (LISt Programming) (67). PROLOG is especially suitable due to its built-in backtracking capabilities and recursive drive. The language is made for goal or rule driven systems. Languages such as PASCAL and C have also been used successfully and due to their widespread familiarity, are preferred by many programmers. Though they may be more common to programmers and may have greater numerical manipulation capabilities, the writer feels that their database management capabilities

and inferencing potential are far inferior to LISP and
PROLOG.

Learning

One of the features of an expert system which requires
special consideration is the ability to deal with new
knowledge. For a system to be considered expert, it must be
able to recognize when it is presented with data which it
does not already contain, and it must be able to place that
data in an appropriate place. An intelligent system must
also be able to accept updated or new rules. Learning may
also include a dynamic database which stores the inferences
made during a given run and recognizes patterns in these
inferences in order to write its own rules. As one may
imagine, learning is the most difficult feature to
incorporate into an expert system.

Expert System Shells

It is well known that the people who design and build
expert systems should be masters of a variety of skills that
take years to develop. The conceptual and technical
difficulty of expert systems originally kept their
development in the hands of a few experienced companies and
research centers around the world. As public awareness of
expert systems grew, however, people wanted a way to build
such systems to solve smaller problems without acquiring a

knowledge engineer and investing the time and money needed to develop a mainframe system. Industrial researchers wanted to spend 90% of their resources on researching the problems at hand and 10% on the computer skills needed to implement a solution.

This demand led to the development of expert system "shells". An expert system shell is a fully developed expert system which has had its knowledge base removed. It contains a variety of user-friendly modifications to assist with the installation of a new knowledge base. Most shells are built for use on personal computers. A person who is using a shell to create a system need not worry about such things as the interpreter or the ordering mechanism because the shell contains a working inference engine. This frees the designer to concentrate on the gathering and representation of knowledge. Loading the rules onto the shell is then fairly straight forward.

It may appear at this point that shells are "too good to be true", but they certainly do have their shortcomings. Shells are built for use on personal computers, thus their biggest drawback is storage capacity. Although shells exist which utilize 128K RAM, most require 640K RAM, thus stretching the capacity of PC's. Although the number of rules which can be included is not severely restricted by such memory constraints, the amount of data stored in tabular format is restricted. The size of the problem which can be solved is constrained by the size of the computer system. A

shell may be used to build a system which assists the assembly of a diesel engine for a truck, but a system to help assemble the entire truck would require too much memory.

How does one know if his problem is of shell proportions? A convenient test is the "phone call" test (2). If the problem can be described to a novice over the telephone with no visual aids in 15 minutes or less, the problem should fit nicely on a shell. This works surprisingly well. A description of greater length generally indicates more rules than the PC can handle. A minicomputer or a mainframe are then needed.

Once the problem at hand has been labeled shell compatible, one must decide which shell to use. This task is not overwhelming because there are only 10-15 shells on the market today and the price range, $50 to $15,000, quickly helps narrow the choices. An in-depth comparison of the various shells and their capabilities has not yet been published so the ability to select an appropriate one is somewhat cognitive. It has been suggested that an expert system to assist individuals in the selection of the proper expert system shell is a problem worthy of further study. When selecting a shell, however, there are several considerations that must be made.

1. The system designer should be aware of how many rules he will generate and the capacity of the shell under consideration. Large problems do not always require many

rules and a large rule capacity does not necessarily indicate a powerful shell.

2. The shell must be compatible with the user's hardware and DOS package.

3. The shell should be adequate for the user's programming skills. Some shells are built for non-programmers while others require extensive computer programming experience.

4. A shell that tolerates certainty factors is usually desired unless it is known that system responses will only be "yes" or "no".

5. Forward or backward chaining is usually dictated by the problem. A system that provides both gives the designer greater flexibility.

6. The user should try to find someone who has the shell he is considering and experiment with it. Many of the shells are personally owned by people who do expert system research. Some manufacturers even supply demonstration disks for a minimal fee.

Appendix II, taken directly from PC World magazine (25), provides valuable information about the top shells on the

market. This information should be beneficial to anyone
looking for a starting point.

Summary

It is realized that the scope of this chapter has been
far too broad to provide an in-depth understanding of expert
system construction. The fundamental concepts and key words
have been provided, and hopefully the basic process of
development has been conveyed. The following chapters will
describe the development of a prototype system in detail and
should shed light on the concepts presented thus far.

CHAPTER 3

AN EXPERT SYSTEM FOR TRENCH SAFETY: THE PROBLEM

The Need For A Proper Analysis of Soil Properties

The ultimate goal of a trench safety analysis is the protection of the workmen in the trench. This generally involves the use of a structure built either to protect the worker from collapsing walls or to prevent the walls from collapsing. The adequacy of any structure built to prevent trench walls from collapsing hinges upon an accurate determination of the lateral soil pressure in the wall. The determination of lateral soil pressure is generally made following a series of laboratory tests.

Traditional Approaches to Soil Analysis

Soil analysis in engineering has traditionally concentrated on classifying soils according to grain size distribution, plasticity, and organic content. These properties are obtained from an analysis of disturbed soil samples and are often augmented with test results taken from undisturbed, in-situ soil. Among the methods most commonly used are the triangular soil classification chart shown in Figure 3.1, developed by the U.S. Department of Agriculture, the AASHTO classification system, shown in Figure 3.2 (derived from a 1920's system utilized by the U.S. Bureau of Public Roads), and the Unified Soil Classification System

Figure 3.1   Triangular Soil Classification Chart
(18, p. 33)

AASHTO Classification of Soils and Soil-Aggregate Mixtures

General Classification	Granular Materials (35% or less passing 0.075 mm)							Silt-Clay Materials (More than 35% passing 0.075 mm)			
	A-1		A-3	A-2				A-4	A-5	A-6	A-7
Group Classification	A-1-a	A-1-b		A-2-4	A-2-5	A-2-6	A-2-7				A-7-5, A-7-6
Sieve Analysis, Percent Passing											
2.00 mm (No. 10)	50 max										
0.425 mm (No. 40)	30 max	50 max	51 min								
0.075 mm (No. 200)	15 max	25 max	10 max	35 max	35 max	35 max	35 max	36 min	36 min	36 min	36 min
Characteristics of Fraction Passing 0.425 mm (No. 40)											
Liquid limit				40 max	41 min	40 max	41 min	40 max	41 min	40 max	41 min
Plasticity index	6 max		N.P.	10 max	10 max	11 min	11 min	10 max	10 max	11 min	11 min[a]
Usual Types of Significant Constituent Materials	Stone Fragments Gravel and Sand		Fine Sand	Silty or Clayey Gravel Sand				Silty Soils		Clayey Soils	
General Rating as Subgrade	Excellent to Good							Fair to Poor			

[a] Plasticity index of A-7-5 subgroup is equal to or less than LL minus 30.

Plasticity index of A-7-6 subgroup is greater than LL minus 30.

Figure 3.2   AASHTO Classification System
(18, p. 35)

Unified Soil Classification System table (rotated):

MAJOR DIVISIONS			GROUP SYMBOLS	TYPICAL NAMES	CLASSIFICATION CRITERIA
COARSE GRAINED SOILS — More than 50% retained on 0.075 mm (No. 200) sieve	GRAVELS — 50% or more of coarse fraction retained on 4.75 mm (No. 4) sieve	CLEAN GRAVELS	GW	Well graded gravels and gravel sand mixtures, little or no fines	$C_u = D_{60}/D_{10}$ Greater than 4; $C_z = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ Between 1 and 3
			GP	Poorly graded gravels and gravel sand mixtures, little or no fines	Not meeting both criteria for GW
		GRAVELS WITH FINES	GM	Silty gravels, gravel sand silt mixtures	Atterberg limits plot below "A" line or plasticity index less than 4 / Atterberg limits plotting in hatched area are borderline classifications requiring use of dual symbols
			GC	Clayey gravels, gravel sand clay mixtures	Atterberg limits plot above "A" line and plasticity index greater than 7
	SANDS — More than 50% of coarse fraction passes 4.75 mm (No. 4) sieve	CLEAN SANDS	SW	Well graded sands and gravelly sands, little or no fines	$C_u = D_{60}/D_{10}$ Greater than 6; $C_z = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ Between 1 and 3
			SP	Poorly graded sands and gravelly sands, little or no fines	Not meeting both criteria for SW
		SANDS WITH FINES	SM	Silty sands, sand silt mixtures	Atterberg limits plot below "A" line or plasticity index less than 4 / Atterberg limits plotting in hatched area are borderline classifications requiring use of dual symbols
			SC	Clayey sands, sand and clay mixture	Atterberg limits plot above "A" line and plasticity index greater than 7
FINE GRAINED SOILS — 50% or more passing 0.075 mm (No. 200) sieve	SILTS AND CLAYS — Liquid limit 50% or less		ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands	
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	PLASTICITY CHART
			OL	Organic silts and organic silty clays of low plasticity	
	SILTS AND CLAYS — Liquid limit greater than 50%		MH	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts	
			CH	Inorganic clays of high plasticity, fat clays	
			OH	Organic clays of medium to high plasticity	
Highly Organic Soils			PT	Peat, muck and other highly organic soils	Visual-Manual Identification. See ASTM Designation D 2488.

Classification on basis of percentage of fines:
Less than 5% Pass 0.075 mm sieve — GW GP SW SP
More than 12% Pass 0.075 mm sieve — GM GC SM SC
5% to 12% Pass 0.075 mm sieve — Border Classification requiring use of dual symbols

PLASTICITY CHART — For classification of fine-grained soils and fine fraction of coarse-grained soil. Atterberg Limits within hatched area indicates a border line classification requiring dual symbols. Equation of A-line $PI = 0.73(LL-20)$

(Plasticity Index vs Liquid Limit chart with A-Line, regions CL, CH, ML or OL, MH or OH, CL-ML)

Figure 3.3 Unified Soil Classification System (18, p. 37)

47

shown in Figure 3.3. The triangular method classifies soils solely on the results of grain size determination. The AASHTO system extends the classification system using the results of liquid limit and plasticity index determinations. Soils containing fines are then subdivided by their Group Index which is calculated using the following equation:

Group Index = (F-35)[0.2 + 0.005(LL-40)] + 0.01(F-15)(PI-10)

where F = percent passing the #200 sieve, expressed as a

whole number

    LL = liquid limit

    PI = plasticity index

The Unified Soil Classification System takes a slightly different approach. Soils are initially divided into three groups: coarse grained, fine grained, and highly organic. Coarse grained soils are divided into gravels and sands based upon their gradation. Fine grained soils are divided using their liquid limit and plasticity index into silts, clays, and organic silts and clays. The value of such a classification will be illustrated below.

Determination of Lateral Earth Pressure

Lateral earth pressure of in-situ soil is a function of the vertical earth pressure times a constant as illustrated by Figure 3.4. This constant is dependent upon the lateral

Figure 3.4 Lateral Earth Pressure as a Function of Vertical
Earth Pressure (18, p. 197)

yielding condition of the soil mass. Soils which have not been subjected to lateral yielding are considered to be in the at-rest state. The constant for the at-rest state, Ko, is a complex function of the overconsolidation ratio, ϕ, and the plasticity index. Figure 3.5 shows an example of the variation of Ko with the overconsolidation ratio for certain soils. Soils subject to lateral compression are in the passive state. The constant for the passive state, Kp, is more difficult to determine. Because the use of retaining structures in trenches involves soils subjected to lateral yielding, but not lateral compression, the derivation of Kp will not be discussed below.

The situation of interest is known as the active state and it occurs whenever a soil deposit yields in such a fashion so as to cause horizontal stretching of the soil. The active earth pressure coefficient, Ka, is obtained from the following equation:

$$Ka = \tan^2(45 - \frac{\phi}{2})$$

where ϕ = the effective angle of intergranular friction

The derivation of this equation requires the shear strength parameters of a soil sample.

The shear strength of a soil sample may be determined using one of three tests: the Consolidated-Drained (CD) test, the Consolidated-Undrained (CU) test, or the Unconsolidated-Undrained (UU) test. For illustrative purposes, the CD direct shear test will be discussed.

50

Figure 3.5 Variation of K_0 with OCR for Some Soils
(18, p. 197)

51

Consolidated-Drained (CD) Test

The soil sample in the laboratory, after having been consolidated under a normal load, N, and allowed to drain, is sheared by a horizontal load, T. This is shown in Figure 3.6. A plot is made of the shear stress, $\bar{\tau}$, required to cause shear failure at various levels of normal stress, $\bar{\sigma}$. Such a plot is shown in Figure 3.7. The data from this plot can be used to draw the Mohr's circle and the Mohr-Coulomb failure envelope for the soil. A sample plot is presented in Figure 3.8. By drawing a circle tangent to the failure envelope for a given pair of $\bar{\sigma}, \bar{\tau}$ conditions, the principal stresses of the sample at failure, $\bar{\sigma}1$ and $\bar{\sigma}3$, can be determined. Ka is de·ived utilizing these stresses as shown in Figure 3.9. Substituting Ka into the equation for lateral earth pressure yields:

$$\bar{\sigma}_a = [\tan^2(45-\frac{\bar{\phi}}{2})] \, \bar{\sigma}_v$$

This equation is valid for all cohesionless soils. For a cohesive soil, the relationship includes a cohesion term:

$$\bar{\sigma}_a = Ka\bar{\sigma}_v - 2\bar{C}\sqrt{Ka}$$

The value of an accurate soil classification system can now be seen. As long as C and ϕ can be determined, soil classification is relatively unimportant. When these values are unavailable, however, a soil classification by one of the methods previously mentioned is critical to the analysis.

Figure 3.6 (CD) Direct Shear Test

Figure 3.7 Results of Direct Shear Test

NORMAL LOAD N	NORMAL STRESS $\sigma = N/A$	SHEAR LOAD T_{max}	SHEAR STRENGTH $\tau_{max} = T_{max}/A$
N_a	σ_a	T_a	τ_a
N_b	σ_b	T_b	τ_b
N_c	σ_c	T_c	τ_c

Figure 3.8   Mohr's Circle Plot of Shear Test

$$\bar{S} = \bar{c} + (\tan\bar{\phi})\bar{\sigma}$$

$$\overline{EC} = \frac{\bar{\sigma}_v - \bar{\sigma}_a}{2}$$

$$\overline{AC} = \frac{\bar{c}}{\tan\bar{\phi}} + \left(\frac{\bar{\sigma}_a + \bar{\sigma}_v}{2}\right)$$

$$\overline{EC} = \overline{AC}\sin\bar{\phi}$$

$$\therefore \frac{\bar{\sigma}_v - \bar{\sigma}_a}{2} = \left(\frac{\bar{c}}{\tan\bar{\phi}} + \left(\frac{\bar{\sigma}_a + \bar{\sigma}_v}{2}\right)\right)\sin\bar{\phi} = \bar{c}\cos\bar{\phi} + \left(\frac{\bar{\sigma}_a + \bar{\sigma}_v}{2}\right)\sin\bar{\phi}$$

$$\bar{\sigma}_v - \bar{\sigma}_a = 2\bar{c}\sqrt{1 - \sin^2\bar{\phi}} + (\bar{\sigma}_a + \bar{\sigma}_v)\sin\bar{\phi}$$

$$\bar{\sigma}_v - \bar{\sigma}_a - \bar{\sigma}_a\sin\bar{\phi} - \bar{\sigma}_b\sin\bar{\phi} = 2\bar{c}\sqrt{(1 + \sin\bar{\phi})(1 - \sin\bar{\phi})}$$

$$\bar{\sigma}_v(1 - \sin\bar{\phi}) - \bar{\sigma}_a(1 + \sin\bar{\phi}) = 2\bar{c}\sqrt{(1 + \sin\bar{\phi})(1 - \sin\bar{\phi})}$$

$$\bar{\sigma}_v\left(\frac{1 - \sin\bar{\phi}}{1 + \sin\bar{\phi}}\right) - \bar{\sigma}_a = 2\bar{c}\sqrt{\frac{(1 + \sin\bar{\phi})(1 - \sin\bar{\phi})}{(1 + \sin\bar{\phi})(1 + \sin\bar{\phi})}}$$

$$\bar{\sigma}_v\left(\tan^2\left[45 - \frac{\bar{\phi}}{2}\right]\right) - \bar{\sigma}_a = 2\bar{c}\sqrt{\tan^2\left[45 - \frac{\bar{\phi}}{2}\right]}$$

$$\therefore \bar{\sigma}_a = \bar{\sigma}_v(K_a) - 2\bar{c}\sqrt{K_a}$$

$$\text{WHERE} \quad K_a = \tan^2\left[45 - \frac{\bar{\phi}}{2}\right]$$

Figure 3.9 Derivation of K_a
(18, p. 201)

56

Determination of the Lateral Force on a Retaining Wall

Once the active lateral stress has been determined, the resultant force against the wall due to a soil mass behind the retaining wall and the point of application of the resultant force can be determined using Rankine theory. Figure 3.10 illustrates a variety of potential situations and the resultant force that occurs due to each situation.

Field Methods of Soils Analysis

The engineer faced with the determination of lateral soil pressures behind a rigid retaining structure thus has well founded methods at his disposal. These methods require an accurate determination of ϕ, the internal angle of friction, and c, the cohesion of the soil. These values are found using the Mohr-Coulomb failure envelope plotted after an analysis of the shear strength. It is an unfortunate economic reality, however, that a contractor involved in short term, light commercial trench operations can seldom afford the time or the cost of a laboratory analysis to provide these values. Peck, Hansen, and Thornburn (44) recognized the need to estimate lateral soil pressure and, as a result, developed the chart presented in Figure 3.11. This chart is based partly on theory and partly on studies of the performance of satisfactory and unsatisfactory retaining walls supporting backfill material. If the conditions on the construction project allow such a chart to be used, then soil classification can be reduced to a visual inspection and

Retaining wall

Lateral Active Pressure Distribution

H

$P_a = \frac{1}{2} K_a \gamma H^2$

$H/3$

$K_a \gamma H$

$\bar{\phi}_1, \gamma_1$

$\bar{\phi}_2, \gamma_2$

$\bar{\phi}_3, \gamma_3$

H_w

H

P_1

P_2

P_3

P_4

$H' = H - H_w$

$K_a \gamma H_w \quad K_a \gamma_b H \quad \gamma_w H'$

$P_1 = \frac{1}{2} \gamma H_1^2 K_a$

$P_2 = \gamma H_1 H_2 K_a$

$P_3 = \frac{1}{2} \gamma_b H_2^2 K_a$

$P_4 = \frac{1}{2} \gamma_w H_2^2$

$P_A = P_1 + P_2 + P_3 + P_4$

Q

H

P_2

P_1

$\gamma_a \gamma H \quad Q$

$P_1 = \frac{1}{2} \gamma H^2 K_a$

$P_2 = Q H K_a$

$P_A = P_1 + P_2$

Figure 3.10 Variations in Lateral Earth Pressure
(18, pp. 204-206)

58

Figure 3.11 Estimating Lateral Soil Pressure
(44, p. 286)

59

categorization into one of four classes. The need for specific values of ϕ and C has been eliminated.

Felix Y. Yokel (58) headed a study for the National Bureau of Standards in 1982 which looked deeply into the problems of safe trench shoring systems in order to provide updated recommendations for OSHA 1926.6, Subpart P. A major concern of the study was the classification of soils into one of four types in order to allow the decision maker to retrieve required timber shoring data from OSHA Table P-2 shown in Figure 3.12. Yokel decided to develop a classification system which meshed with the work done by Peck and others, thereby providing a procedural method of classification and an associated lateral soil pressure determination. The method developed for classifying the soil is called the Matrix Classification System and is shown in Figure 3.13. The soil is classified as Type I, II, III, or IV based upon site conditions such as the presence of water and fissures as well as the properties of the soil.

As a result, the soil is placed in one of four categories: stiff cohesive, medium cohesive, granular, and soft. Yokel then assigned a value to each soil type known as the lateral weight effect, We, which is displayed in Figure 3.14. These values are taken from Peck's chart utilizing an intermediate, constant slope angle and setting We = (0.6)Kh. Yokel also recommended using the rectangular pressure diagram shown in Figure 3.15 as the basis of force calculations. This approximation is necessary because of the effects of

60

TABLE P-2

TRENCH SHORING—MINIMUM REQUIREMENTS

Depth of trench	Kind or condition of earth	Uprights		Stringers		Size and spacing of members							
						Cross braces [1]						Maximum spacing	
						Width of trench					Maximum spacing		
		Minimum dimension	Maximum spacing	Minimum dimension	Maximum spacing	Up to 3 feet	3 to 6 feet	6 to 9 feet	9 to 12 feet	12 to 15 feet		Vertical	Horizontal
Feet		Inches	Feet	Inches	Feet	Inches	Inches	Inches	Inches	Inches		Feet	Feet
5 to 10	Hard, compact............	3x4 or 2x6	6	....		2x6	4x4	4x6	6x6	6x8		4	6
	Likely to crack............	3x4 or 2x6	3	4x6	4	2x6	4x4	4x6	6x6	6x8		4	6
	Soft, sandy, or filled........	3x4 or 2x6	Close sheeting	4x6	4	4x4	4x6	4x6	6x6	6x8		4	6
	Hydrostatic pressure........	3x4 or 2x6	Close sheeting	3x8	4	4x4	4x6	6x6	6x8	8x8		4	6
10 to 15	Hard............	3x4 or 2x6	4	4x6	4	4x4	4x6	6x6	6x6	8x8		4	6
	Likely to crack............	3x4 or 2x6	2	4x6	4	4x4	4x6	6x6	6x8	8x8		4	6
	Soft, sandy, or filled........	3x4 or 2x6	Close sheeting	4x6	4	4x6	6x6	6x6	8x8	8x10		4	6
	Hydrostatic pressure........	8x6	Close sheeting	8x10	4	4x6	6x6	6x6	8x8	8x10		4	6
15 to 20	All kinds or conditions......	8x6	Close sheeting	4x12	4	4x12	6x8	8x8	8x10	10x10		6	6
Over 20	All kinds or conditions......	8x6	Close sheeting	6x8	4	4x12	6x8	8x8	8x10	10x12		6	6

[1] Trench jacks may be used in lieu of, or in combination with, cross braces.
Shoring is not required in solid rock, hard shale, or hard slag.
Where desirable, steel sheet piling and bracing of equal strength may be substituted for wood.

Figure 3.12   OSHA 1926 Table P-2
(61, p. 198)

61

Table 5.3 Soil Classes in Matrix Classification System

Site Condition Soil	Water in Trench			
	No		Yes	
	Fissures		Fissures	
	No	Yes	No	Yes
Stiff Cohesive[a/]	I	II	III	
Medium Cohesive[a/]	II	III	III	IV
Granular[b/]	II		III	
Soft	IV		IV	

Notes:

1. **Water in Trench** is assumed whenever water drains into the trench from the soil forming the bank, or water is retained by tight sheeting, or there is a possibility that the trench may become fully or partially flooded before workers leave it, or may be entered by workers within 6 hours after more than half its depth was flooded and pumped out.

2. **Vibrations**: Soils subject to vibrations by heavy traffic, pile driving or similar effects shall _always_ be assumed _fissured_.

3. **Stiff Cohesive Soils**[a/] include stiff clays and cohesive or cemented sands and gravels (till, hardpan). Stiff clays included have an unconfined compressive strength (pocket penetrometer reading) q_u = 1.5 tsf[c/] or larger.

4. **Medium Cohesive Soils**[a/] have an unconfined compressive strength (pocket penetrometer reading) between 0.5 and 1.5 tsf[c/].

5. **Granular Soils**[b/] are gravels, sands and silts that can stand on a slope steeper than 3 hor.: 1 vert. without spalling or slumping.

6. **Fractured Rock** shall be treated as granular soil. Intact rock is exempt from shoring and sloping requirements.

7. **Soft Soils** are cohesive soils [a/] with an unconfined compressive strength (pocket penetrometer reading) of 0.5 tsf[c/] or less and granular soils that can not stand on a slope of 3 hor.: 1 vert. without slumping (muck).

8. **Layered Systems** (two or more distinctly different soil or rock types, micaceous seams in rock) which dip toward the trench wall with a slope of 4 hor.: 1 vert. or steeper are considered Class IV soils.

9. **Distrubed Cohesive Soils** (backfill) shall be treated as _fissured medium cohesive_ or _soft cohesive_ soil.

10. **Spaced Shoring Systems** (skeleton sheathing or skip shoring) are permitted in _stiff and medium cohesive soil_ with maximum center to center spacing in accordance with Table 5.5.

[a/] Cohesive Soils are clays (fine grained) or soils with a high clay content which have cohesive strength. They do not crumble, can be excavated with vertical sideslopes, are plastic (can be molded into various shapes and rolled into threads) when moist and are hard to break up when dry.

[b/] Granular Soils have no cohesive strength. They normally can not be excavated with vertical sideslopes (some moist granular soils will exhibit apparent cohesion and temporarily stand on a vertical slope), they can not be molded when moist and crumble easily when dry.

[c/] 1 tsf = 96 kPa

Figure 3.13 Matrix Classification System
(58, p. 85)

62

```
*********************************************************************
```

SOIL TYPE		LATERAL WEIGHT EFFECT We in (lb./ft3)
I	--	20
II	—	40
III	—	60
IV	—	80

```
*********************************************************************
```

Figure 3.14 Lateral Weight Effects
(58, p. 89)

p = We (H + 2)

P = p X H

H = Height of Supported Bank (ft.), 2ft. are added to allow for surcharge

p = Distributed Horizontal Earth Pressure (lb./ft^2)

P = Resultant Horizontal Force per Unit Length (lb./ft.)

We = Lateral Weight Effect (lb./ft^3)

Figure 3.15   Rectangular Pressure Diagram
(58, p. 35)

wall flexibility and variations in construction sequence.
Less conservative shapes are precluded (56).

The heuristic classification system and determination of
lateral soil pressures provide an obvious benefit to the
contractor. Although the values obtained are perhaps overly
conservative, the contractor need not concern himself with a
lengthy laboratory analysis and may obtain enough information
in a matter of minutes to assemble a timber shoring system or
select a proper slope angle. A disadvantage which is not so
obvious stems from the conservative nature of the approach.
The disadvantage is discussed later in this chapter.

Methods of Trench Wall Stabilization

A contractor has many methods of trench wall
stabilization at his disposal. Among the less common are
stabilization by injection, electroosmosis, and freezing.
Readers interested in any of these three methods are referred
to General Excavation Methods, by A. Brinton Carson (7).
Slightly more common is the use of sheet piles, driven before
excavation, and soldier beams, driven as individual piles and
spaced to allow for the insertion of timber planks as
sheeting. It is the writer's opinion that these methods are
too time consuming and expensive for use in short term trench
operations Most contractors employ trench boxes, sheeting
with trench jacks (hydraulic or manual), timber frame
shoring, or bank sloping.

Bank Sloping

A contractor opting to slope the trench banks may utilize any one of three allowable configurations shown in Figure 3.16 to comply with federal regulations (59).

Timber Frame Shoring

A contractor choosing to construct a timber frame shoring system is guided by OSHA 1926, Subpart P, Table P-2 (61). This table was presented as Figure 3.12. As Figure 3.12 indicates, sheeting, wale, and strut requirements are dictated by the depth of the trench and a visual classification of the soil. Yokel (56) has provided a replacement for these classifications with soil Types I, II, III, IV. Therefore, a procedural method of shoring member selection is available. A common arrangement of the members required using Table P-2 is conceptualized in Figure 3.17.

Inconsistencies With Current Tabular Methods

Identification of Inconsistencies

Initial efforts by the writer to develop an expert system prototype to enhance the selection of timber frame shoring attempted to apply the matrix classification system, obtain a lateral earth pressure and a required shoring design, and then select a suitable type of lumber by applying

Figure 3.16   Allowable Sloping Configurations
(59, p. 12)

Figure 3.17 Typical Timber Shoring Design

well known equations of shear, compression, and elastic modulus to the wood structural members. Initial runs of the system revealed stresses that were so high that lumber with the required strength did not exist and thus no recommendations could be made. A thorough review of the work done by NBS led to personal correspondence with Dr. Yokel to determine if he had encountered similar difficulties. A copy of the letter and the calculations forwarded to him are enclosed in Appendix 3. The immediate question raised was that of functionality. According to the analysis, the timber shoring recommendations provided by Table P-2 should be failing frequently, yet that has not been the case. An ensuing phone conversation with Dr. Yokel revealed that an examination of the calculations used to develop Table P-2 would not be possible. He stated that he too had been unable to verify the table using a similar analysis. OSHA Table P-2 had evidently been empirically developed from a series of regional interviews with contractors in an effort to define "what works."

Dr. Yokel's study resulted in several proposed revisions to the table (58) and they were forwarded to OSHA for inclusion in a revised instruction in 1982. The revised instruction has as yet not been released.

Explanation of Inconsistencies

To answer the question of why the analysis performed in Appendix 3 and reviewed by Dr. Yokel could not substantiate

well tested designs, it is necessary to re-examine some of the assumptions made up to this point.

First and foremost is the conservative nature of the classification system and the method used to assign the lateral weight coefficients.

Second, although it would be difficult to justify another shape, the rectangular pressure diagram assumption is obviously conservative.

Third, the assumption that the shoring could be analyzed as a beam on rigid supports probably does not reflect the actual field conditions. It is a well known fact that timber deflects substantially under loads. This flexing relieves and reapportions the pressures in the trench wall. An analysis of the shoring system as a beam on flexible supports might therefore provide a better understanding of the stresses involved. This analysis would be quite problem dependent for it would have to consider many factors about the moisture content and properties of the specific wood used as well as the compressive properties of the soil so that spring constants could be obtained. Although lengthy, the analysis might provide a better method of tabularizing timber shoring designs. It should be noted that such an analysis was not conducted as a part of this research because the focus was not the in-depth study of timber frame earth retaining structures, it was rather an application of expert system technology to existing expertise. Such a thrust, however, can be suggested as an area for future research.

Affect On Expert System Development

Because of the writer's inability to accurately define a set of equations which would enable the calculation of sizes of timber shoring members, this planned capability of the prototype expert system was deleted. Instead, it was decided that the system would utilize the member sizes suggested by OSHA, Table P-2 which makes no recommendation concerning the most suitable **type** of lumber. This table remains the legal standard and although it is not well supported by engineering calculations, it has worked satisfactorily in the past.

Elements of Trench Safety Not Related To Shoring

Miscellaneous Safety Features

Although bank stabilization is a primary element of trench safety, there are other factors to be considered in an overall safety analysis. During the project planning and the construction stages, a contractor must be fully aware of safety equipment and construction practices that may affect the safety of his jobsite. The location of utility lines and the development of emergency procedures to be followed when a line is unexpectedly broken merit concern. The improper removal of surface encumbrances, such as stumps and boulders can present hazardous conditions. Mobile equipment which may be operating at or near the edge of the trench mandates particular caution. The proper placement of walkways,

bridges, ramps, ladders, and barriers are often overlooked on small jobs. Hazardous dusts, gases, fumes, and oxygen deficiencies may require the use of special equipment such as explosimeters and respiratory masks. It has been the writer's personnel experience that standard personal protective equipment such as hardhats, goggles, and gloves are perhaps the easiest items to obtain, yet seem to be the items most often neglected. A thorough, periodic safety inspection should account for all of these items.

Construction Site Practices

In addition to the features of the trench operation which require particular attention, there are often adjacent operations on the site which may greatly influence trench stability. Blasting on the site changes the character of the soil and the pressures in the trench walls. Rapid dewatering may create quick conditions on the floor of the trench. The storage and retainage of spoil bank material excavated from and piled next to the trench may alter the stability of the trench wall. Such practices create falling object hazards if the material is positioned improperly. The overall safety inspection routine followed on the project to monitor these practices will definitely enhance or detract from the trenching operations.

Summary

The safety of a workman in a trench is dependent upon a thorough investigation of all of these items discussed in this chapter. If standards are to be satisfied, soil analysis, bank stabilization, miscellaneous safety features, and proper construction practice must all be examined. The complexity of this analysis warrants special expertise. Chapter 4 proposes a unique application of a new technology to provide such expertise.

CHAPTER 4

SFTYCHEF: AN EXPERT SYSTEM PROTOTYPE FOR TRENCH
SAFETY ANALYSIS

Problem Definition

Chapter 3 presented the various components of the
situation faced by a contractor who is trying to provide a
safe trench environment for trench workers. The contractor
must perform a soil analysis to determine the engineering
properties of the soil. Time and expense lessen the
likelihood of using laboratory techniques so they often
rely on experience or systems such as the Matrix
Classification System. The soils analysis data must then be
combined with trench parameter data to determine proper
sloping angles or to provide a tabular determination of an
adequate shoring design. Optimally, the contractor should
design shoring systems based on particular jobsite and
material conditions. However, as was discussed in Chapter 3,
this problem is not a simple one. In addition, individual
design is discouraged because the provisions of OSHA 1926
Table P-2 provide sufficient, though over-designed, systems.

After a shoring system or slope angle has been selected,
the contractor must carefully consider the site conditions
and construction methods in order to determine if particular
safety equipment or specialized safety procedures are

74

required. The contractor who performs these tasks in earnest greatly reduces the risk of accidents on his jobsite.

SFTYCHEF was designed to provide consultative, diagnostic assistance to the contractor in making the necessary decisions. It performs the soil analysis using the Matrix Classification System, gathers trench parameter data, site specific information, construction method information and then evaluates the overall operation as either being safe or unsafe. It also performs a table look-up and provides the contractor with an implementable shoring design and an acceptable slope angle. A list of safety notes is also furnished. These highlight the specific safety equipment the contractor must utilize and any specific safety procedures which must be followed. References to sources of more specific information are also provided. SFTYCHEF has a narrow set of suitable situations in which it can be used, however. SFTYCHEF was specifically designed for:

1. Trench operations in which the trench is open for 24 hours or less.

2. Trenches whose depth does not exceed 20 feet.

3. Trenches which are not located near an adjacent, existing foundation.

4. Trenches which are not located in climates
characterized by excessive amounts of rainfall.

SFTYCHEF helps the contractor identify the features of a
safe operation. The contractor must then implement the
recommended actions.

Knowledge Base

Knowledge Acquisition

The basis of the complete and verifiable knowledge
included in any expert system hinges upon the dedication of
an expert or experts to the system development. Expert
dedication exceeds the scope of an interested faculty member
or a quick learning student. Periodic interviews also seldom
provide the needed interaction. Ideally, the expert should
be the one with the problem which the system will solve. The
expert's knowledge, perhaps verified by his status as a
Professional Engineer and years of experience, provides the
basis from which the knowledge engineer will develop the
system. It is often true that the knowledge engineer becomes
an expert in the domain as he constructs the system. This is
a result of the continuous interaction with the expert. It
is illogical to assume that true expertise can be extracted
from a novice. In the words of G.L. Simons (51), "It is
certainly possible for an incompetent to create an
incompetent expert system."

It should be noted that the development of SFTYCHEF was not supported by a dedicated expert. This lack of expert interaction represents its major weakness at this stage of its development. The knowledge to construct the system was acquired via the writer's own course work, literature search, and personal experience. Attempts were made to utilize expertise from within OSHA, the U.S. Navy Civil Engineer Corps, and the U.S. Army Corps of Engineers, but to no avail. This was not particularly surprising since the work was an unsponsored research project. Often researchers have an inflated view of the importance of their work and expect instant support from others. Unfortunately, this view is seldom shared by outside agencies, unless great advantage is to be obtained through active participation.

The knowledge contained in SFTYCHEF is, however, not inaccurate because all knowledge was extracted from creditable sources. The completeness of the knowledge base is, however, suspect. J. McDermott (38), designer of R1, a system which configures VAX 11/780's for the Digital Electronics Corporation, constructed a knowledge base of approximately 200 rules on his own, using personal expertise and literature review. After a two month period of daily interaction with experts, the knowledge base tripled. SFTYCHEF would probably also benefit greatly from such a period of interaction.

Knowledge Representation

As information relevant to the problem was initially being acquired, much thought was given to the use of semantic nets, state-space, or logic representation schemes. It was quickly discovered that the overwhelming amount of information did not fit quickly or conveniently into such formats. Current literature does not provide any practical instructions on how to collect and represent the knowledge. Perhaps this report can alleviate a portion of the difficulties involved.

The procedure developed by the writer included a large chart which was placed on a wall. The chart was approximately 8 feet by 6 feet in size and was made of white posterboard. The top center of the posterboard was labeled with the system objective and below that, subgoals were placed on separate pieces of posterboard and connected with lines to the main objective. Figures 4.1 and 4.2 serve as a basic illustration. As knowledge was collected, it was listed quite randomly at first under the subgoal to which it pertained. As the boards began to fill up, it became easier to see patterns and relationships among the information. The use of separate boards for each subgoal was essential, because at some point, the boards could then be taken off the wall, reorganized and replaced by a new board. Each board eventually looked like either a decision tree, a listing of conditions, a listing of facts, or a combination of rules.

At this stage, the scope of the problem was refined

Figure 4.1   Wall Chart Schematic: Primary Subgoal Level

. . . .

SHORING DESIGN	SLOPING CRITERIA	SAFETY FEATURES	CONSTRUCTION METHODS
↑	↑	↑	↑

```
OSHA TABLE        USER INPUTS    -UNDERGROUND    -EXCAVATED
   P-2              -DEPTH         UTILITIES       MATERIALS
                    -WIDTH        -SURFACE        -WALKWAYS,
                    -HORIZONTAL    ENCUMBERENCES   RUNWAYS, &
                     CLEARANCE    -MOBILE          SIDEWALKS
USER      MATRIX                   EQUIPMENT      -INSPECTION
INPUTS    SOIL                    -BARRICADES     -WATER
          CLASS.                  -WALKWAYS &      REMOVAL
DEPTH                              BRIDGES        -BLASTING
WIDTH      -FISSURED SOIL         -RAMPS          -DUST
           LAYERED SOIL           -LADDERS         ELIMINATION
           SOFT SOIL              -PERSONAL
           GRANULAR SOIL           PROTECTIVE
           WET SOIL                EQUIPMENT
           COHESIVE SOIL          -VEHICULAR
                                   TRAFFIC
                                  -RESPIRATORY
                                   HAZARDS
```

. . . .

Figure 4.2   Summary of the Factors Involved in Each of the
              Safety Analysis Subgoals

80

several times. What originally seemed to be a very narrow problem seemed to have an abundance of rules and facts. The reader can get an immediate feel for this problem by spending a few minutes listing out the rules to be used to distinguish a pen from a pencil. There are many ways to handle this trivial distinction, which at its fundamental level, may not be so trivial.

Once the knowledge was sufficiently refined and the diagram began to take structure, the search for new knowledge became much more guided. Eventually the diagram was complete enough so that cause-effect relationships could be determined using all of the information acquired. This made rule writing in an IF-THEN format much easier.

Language Implementation

SFTYCHEF is a pure production system implemented using EXSYS (20), an expert system development shell. Knowledge is loaded into EXSYS directly in the form of IF-THEN rules. The rules are developed by creating a series of qualifiers and selecting the components of the qualifiers to build a rule. Figure 4.3 presents two qualifiers and Figure 4.4 demonstrates how they are used to create a rule.

The rules loaded into EXSYS were taken directly from the wall diagram. The rules were somewhat modularized due to the separation of subgoals on the diagram, but modularity is not necessary. A pure production system requires no rule ordering.

```
**********************************************************************

QUALIFIER #X

    The primary composition of the excavated soil is

    1.   Fractured Rock

    2.   Sand

    3.   Silt

    4.   Gravel

    5.   Cohesive Soil


**********************************************************************

QUALIFIER #Y

    The soil classification must consider

    1.   Layered Soil

    2.   Soft Soil

    3.   Medium Cohesive Soil

    4.   Wet Soil

    5.   Fractured Soil


**********************************************************************
```

FIGURE 4.3   SAMPLE QUALIFIERS

****

RULE #Z:

IF: The primary composition of the excavated soil is **silt,**

THEN: The soil classification must consider **soft soil.**

****

FIGURE 4.4   SAMPLE RULE USING QUALIFIERS #X AND #Y
FROM FIGURE 4.3

Additional features of EXSYS will be brought to light in later sections of this chapter. Chapter 5 contains a section of evaluative comments concerning its capabilities. Those interested in learning how to use EXSYS and the particular aspects involved with the loading of a knowledge base should read the EXSYS, Expert System Development Package manual (20). EXSYS is also accompanied by three tutorial sample diskettes which are very informative

Inference Structure/Chaining Mechanism

SFTYCHEF utilizes backward chaining through its knowledge base of p oduction rules to make inferences One of the greatest assets of EXSYS is the capability to both forward chain or backward chain. The problem addressed by SFTYCHEF is one of diagnostics, thus being goal driven This warrants the use of backward chaining.

During a consultation session, the interpreter selects the two goal nodes, **Safe** and **Unsafe**, and backward chains through the production rules via matching consequents and antecedents until rules are selected which require user supplied data. The search strategy employed by SFTYCHEF is top down, depth first. To illustrate this, an example can be presented.

Once the goal nodes are selected at the outset of a consultation session, all rules whose consequents include Safe or Unsafe are brought forth from the knowledge base.

One of these rules might be

RULE 018 IF the safety analysis reveals a sloping
                criteria which can be met
          THEN Safe   Probability = 9/10
           AND Unsafe   Probability = 1/10
          ELSE Safe   Probability = 1/10
           AND Unsafe   Probability = 9/10

SFTYCHEF must now evaluate this group of rules so it
begins by trying to verify the antecedents of the first rule
selected   Assume that rule 018 was the first rule, it would
search the database and call forth all rules which provide
information on the sloping criteria. One of these rules
might be

RULE 031: IF the depth of the trench is 5-10 feet
             AND the class of the soil is type II
             AND [Clearance] >= 7.5
             THEN the safety analysis reveals a sloping
                  criteria which can be met

SFTYCHEF will try to evaluate the antecedents of rule
031 which will in turn verify rule 018. SFTYCHEF will not
try to evaluate the second rule which was selected with rule
018 until it has been determined that rule 018 cannot be
satisfied. This is what is meant by a depth first search.

Antecedents 1 and 3 of rule 031 require user input for verification. [**Clearance**] is the distance in feet from the edge of the trench to the nearest obstruction which might prevent excavation. SFTYCHEF asks the user for this information. Antecedent 2 calls another list of rules whose consequents classify the soil as type II. SFTYCHEF continues in this manner until a rule is reached whose antecedents can all be verified. The firing of this rule causes the path of rules to the goal node to fire as well.

During the design of a knowledge base, EXSYS allows the use of two rule selection modes, **First Rule**, or **All Rules**. First Rule causes the analysis to proceed as discussed above and the first rule to succeed among the group containing rule 018 causes an evaluation of Safe or Unsafe and the session stops. All Rules places the first evaluation on hold and proceeds to check the others as if rule 018 had not been verified. It then combines the conclusions of all of the rules on the level of rule 018 before making an analysis. SFTYCHEF should always be utilized in the All Rules mode.

Explanatory Capabilities

SFTYCHEF's explanatory capabilities are designed to respond to two types of user queries. The user may request information about a particular parameter during the consultation. He may also desire an explanation of the conclusions output at the end of the session.

Questions of the first type cause a display of the
current rule which the system is evaluating. The rule may
contain a textual note which clarifies the rule. The rule
may also contain a reference telling the user where the
information for the rule was acquired.

A question of the second type causes the system to
display a list of rules whose consequents directly affected
une output in question. The user may prompt the system for
information on the derivation of any of those rules as well.
The listing of rules quickly becomes confusing to a first
time user so a few guidelines should be followed.

1. At the end of a consultation, questions regarding
conclusions can be answered by typing in the number of
the conclusion in question and striking the return key.

2. Should the first rule or group of rules answer the
question, repeated striking of the return key will lead
to the output display.

3. If there is a question regarding the derivation of
any of the rules from step 2, an answer may be obtained
by typing in the number of the antecedent in question
while the rule is displayed, and then striking the
return key. SFTYCHEF will then list all the rules fired
to determine all of the antecedents of the rule in
question. This provides the user with much more

information than was originally requested.

4. A query into any of these rules pushes the explanation one level deeper. It is not difficult to become lost in the explanation. Some practice is required to extract exactly what is desired as quickly as possible.

SFTYCHEF has a built-in feature which should alleviate much of the need for the second type of question. Many of the rules have dummy string variables attached to them. Should one of these rules fire, the text string is output with the results. This can easily be used to alert the user to missing data or points of caution. SFTYCHEF also contains an on-line help facility which reviews most of the procedures discussed here.

Confidence Factors

Confidence factors are used to a limited extent by SFTYCHEF. Any knowledge base built using EXSYS may utilize one of three modes of goal selection. The first is a Yes/No mode which merely assigns a value of yes or no to a choice. The second mode assigns a value between 0 and 10 to a choice. A value of 0 designates absolutely no, while a value of 10 designates absolutely yes. Values from 1 to 9 allow degrees of certainty to be expressed. The third mode assigns a value

between -100 and +100 to a choice. Modes 2 and 3 require a combinatorial scheme for rules which derive similar conclusions with varying certainty. In the 0 to 10 mode, the confidence factors are simply averaged. An assignment of a 0 or a 10 to a choice by any rule, however, excludes all other confidence factors from consideration. In the -100 to +100 mode, confidence factors can be averaged or they can be combined as dependent or independent probabilities. In this mode, there are no absolutes.

A major drawback of EXSYS is that confidence factors can only be attached to rules which directly affect the final goal. In rule 018, values of 1 and 9 were attached to the selection of Unsafe and Safe. It is not possible, however, to attach confidence factors to a rule such as rule 031 which verifies rule 018. This means that uncertainty can only play a role in the selection of a goal and that the verification of subgoals must be considered absolute. This is a limiting feature.

SFTYCHEF utilizes the 0 to 10 mode and contains confidence factors for each of the rules whose consequents are goal states. The values of the confidence factors were assigned at the designer's discretion and require some clarification. As was explained earlier, the final selection of Safe or Unsafe is determined by the evaluation of four subgoals. Two rules were written. For one of them, all four subgoals were true and for the other, all four subgoals were false. The goals were given confidence factors of 10 and 0

89

respectively. Four rules contain one subgoal each as their antecedent. The confidence factor assigned to the goal depends upon the criticality of the subgoal to the safety of the trench. If only the shoring system were considered, Safe would receive a value of 9. If only the equipment were considered, Safe would only receive a 7. Of course in system processing, all four subgoals are evaluated. Unless all are true or all are false, the values of Safe and Unsafe provided are an average of those assigned by the four individual rules. A careful examination of rules 015-020 in Appendix IV will clarify this concept.

Incomplete Knowledge

Whenever user input is unknown, SFTYCHEF defaults to the worst case value of the requested input. In this manner, SFTYCHEF can provide an analysis even though all knowledge is not available. At the end of a consultation, the user is reminded of the information which was not known and the affect which this may have had upon the outcome. The assignment of worst case values was viewed as the only reasonable alternative in a system which evaluates safety.

Addition of New Knowledge

The fact that SFTYCHEF is a pure production system means that the addition of new knowledge is quite simple. Rule

ordering is of no importance, therefore new rules can be
added at the end of the knowledge base. Deletion of existing
rules is also quite simple. The tradeoff for this
convenience is a loss of modularity which not only would make
the system more readable, but would also decrease runtime and
allow for more accurate pruning of unnecessary questions.
For a shell based system the size of SFTYCHEF, however, these
tradeoffs are minimal.

Summary

SFTYCHEF will assist the contractor involved in
trench excavations on light commercial construction projects
in performing a safety analysis. The system is a production
system built using EXSYS, one of the commercially available
expert system shells. SFTYCHEF backward chains from two goal
nodes, Safe and Unsafe, to collect required user input and to
make a diagnosis. SFTYCHEF can explain its reasoning, make
educated guesses supported by confidence factors, and provide
a diagnosis in spite of missing information. The knowledge
base is flexible in that new rules may be added or existing
ones may be deleted. Chapter 5 presents a tutorial for
SFTYCHEF and a detailed explanation of its output. Chapter 6
discusses the future work to be done on SFTYCHEF as well as
the merits of EXSYS.

CHAPTER 5

SFTYCHEF: A TUTORIAL

Summary of Key Points

At this point, the reader should have a sound
understanding of the principles behind expert systems, the
problems involved in safe trench operations, and the
capabilities of the expert system prototype, SFTYCHEF. A
copy of SFTYCHEF is contained in a pocket on the inside of
the back cover of this report. It should not be overly
optimistic to assume that the reader could now utilize the
system given some basic guidance. In order to facilitate a
deeper understanding of the system, however, this chapter
will lead the reader through a simple scenario and a tutorial
run. Before commencing with the scenario, it is important to
summarize the key ideas discussed to this point upon which
SFTYCHEF will rely.

The fundamental objective of the system is to provide
consultative assistance to light commercial construction
contractors performing a safety analysis on a trench
excavation. The intended result is a scaled rating of SAFE
or UNSAFE provided to the contractor.

The safety of the operation is determined after a
thorough evaluation of four key aspects: (1) timber shoring
design, (2) proper angle of repose, (3) appropriate safety

equipment, and (4) hazardous construction site practices.

SFTYCHEF backward chains through its rules until it reaches rules which require user input. The user is asked for information concerning various aspects of the job. SFTYCHEF utilizes a portion of the input to perform a soil analysis via the Matrix Classification System (56) detailed in Chapter 3. It combines the classification of the soil with the trench depth and width to extract a suitable timber shoring design from OSHA publication 1926, Subpart P, Table P-2 (61). A useable angle of slope is also calculated from the input data. The required safety equipment and hazardous construction practice warnings are drawn directly from OSHA publication 1926, Subpart P (61).

The user should be familiar with the construction project before consulting SFTYCHEF. The most advantageous time to use the system is after the trench has been excavated, but before any work in the trench has begun. It may, however, be used at any stage of operations. The user will need to consult the plans and specifications for the project. The user must be familiar with the project job plan, neighboring activities, site conditions, and personnel assignments. The only technical data requested is the result of a pocket penetrometer test. The unavailability of this data will not preclude an analysis but will weaken the confidence of the results.

In addition to a rating of SAFE or UNSAFE, SFTYCHEF will provide a useable timber shoring design, an allowable slope

angle, a listing of required safety features, and commentary on potentially hazardous construction practices. Those using the system only to obtain a shoring design are reminded that 75% of the system will not be utilized since it is dedicated to the overall analysis of safety.

Scenario

A contractor is faced with a trench excavation which he knows will require some analysis of safety and a shoring system, but he is not completely familiar with the items to be evaluated. No one on his small staff has the required expertise so he decides to consult SFTYCHEF as the job progresses.

A walkthrough of the site before excavation began revealed a gently sloping, lightly vegetated site with no trees, large boulders, or obstructions. The ground surface was dry. A country road cuts across the site, but passes no closer than 47 feet to the trench. The contractor noted a slight concern for men working near occasional traffic.

The planned trench is to be 200 yards long, 12 feet deep at its maximum, and less than 7 feet wide to facilitate the installation of a gravity flow sewer line. Underground utilities are not expected to be a problem. No supporting earthwork will be necessary.

The job will progress quickly and can be done with 2 backhoes and a front-end loader. The trench needs to be

bridged at one point near the middle to allow workers to cross. One end of the trench is to slope up to ground level so no ramps or ladders are needed. The only other work on the site involves material hauling and staging by flatbed trucks. The assigned safety inspector has thoroughly analyzed the job and has pointed out a possible dust hazard and a potential fume problem. Oxygen deficiency or flammable gases cause no concern. Figure 5.1 depicts this particular project in plan view and in elevation.

After excavation begins, the trench walls reveal a homogeneous soil of clay-like consistency. The soil is moist and does not spall or flake off the trench wall. Vegetation or previous disturbances have not seriously fissured the soil. A handful of the excavated soil can be molded with strong finger pressure and penetrated with the thumb with moderate effort. The excavation foreman reports a penetrometer reading of 1.30 tons per square foot. With this information available, the contractor can utilize SFTYCHEF.

Tutorial Run

User's Instructions

The description of the tutorial run refers regularly to screens displayed by the system. Printouts of these screens are included at the end of this chapter and should be referred to continually. Best results are achieved when the reader runs the system along with the tutorial.

Plan View – Not To Scale

S.R.302

1560

47'

600'

Temporary Bridge

Light Vegetation

7'

₵

Proposed Trench

1565

1560

Profile View – Not To Scale

Ground Surface

Bridge

1562

8'

12'

600'

Homogeneous Clay

Trench Floor

Figure 5.1   Scenario Sketches

SFTYCHEF is on a single floppy disk and is self booting so that the user needs no other disks. The only equipment required is an IBM Personal Computer with a minimum of 256K RAM and one floppy disk drive. Any IBM compatible system will also work. A monochrome or multicolor screen can be used. A printer is helpful but is not necessary.

Loading the system is not difficult. The disk is first inserted into the floppy drive, label side up and the notched side on the left of the user. After inserting the disk and closing the dust cover, the PC is turned on. The system takes over from there. The PC will first request the current date. Pressing the RETURN key twice at this point obtains the A-prompt (A>).

At the A>, the user should type the words EXSYS SFTYCHEF with one space between them. They need not be typed in capital letters. After hitting the RETURN key once more, the system takes over and Screen 1 is displayed.

Screen Analysis

Pressing any key causes Screen 2 to be displayed. A first time user of SFTYCHEF should answer yes to this first question. The system has excellent instructions contained in an initial, brief presentation.

Following the instructions, or by answering no, Screen 3 is displayed. Unless one is doing in-depth study of the system and its rules, one should always answer no or hit return when asked if a rule display is desired. Answering

97

yes causes an overabundance of unnecessary information to be presented to the user and triples the time needed for a run. Screens 4 and 5 complete the introduction and Screen initiates the analysis.

SFTYCHEF asks the user questions by displaying a list of options to the user. The user answers the question by typing the number of the desired response and hitting RETURN. SFTYCHEF refers to the RETURN key as ENTER. Multiple answers are permitted, where appropriate, and are entered by typing all of the desired numbers, separated by commas.

The menu at the bottom of Screen 6 appears with every question. Typing WHY instead of a number prompts the system to display the series of rules which it is using to reach a conclusion. This will be investigated later. Typing QUIT allows the user to save all of his input data to this point, turn off the the system, and return to it later. Typing <H>, help, provides the user with further guidance.

As displayed in Screen 6, the proper response for the scenario is 3, 10-15 feet, thus 3 and ENTER were typed. Screens 7 to 35 were generated using the data from the scenario and should be carefully reviewed by the reader.

Screens 9 to 13 provide an example of what is produced when WHY is typed. Screens 10, 11, 12, and 13 display the rules which the system is trying to evaluate at this point. Typing ENTER causes the screens to advance.

It should be noted in Screen 10 that the menu at the bottom has changed. Input of a line number in the IF

condition will display all rules used to verify or refute that condition. <K> causes a listing of all known data input so far. <C> lists the users choices for Screen 9. <R> provides the textual reference from which the rule was obtained. ↑ or ↓ displays the next consecutive rule, <J> jumps to a rule of the user's choosing. At this point, the user should merely type ENTER and proceed.

A sample of a multiple response is shown in Screen 22. The response indicates that there is some threat of hazardous dusts or fumes.

Completion of the scenario brings the user to Screen 36. Screen 36 briefly introduces the results of the analysis which will follow.

Screens 37, 38, and 39 are the results of the analysis and should be carefully read.

Line 1 of Screen 37 gives the operation a rating of SAFE with a value of 10, the highest attainable. Lines 2 through 8 provide shoring information. The rest is self explanatory.

The bottom of Screen 39 reveals a new menu. <H> will explain what each choice will do. At this point, the user should type <C>, which will allow him to change any input data and rerun the system.

In screen 40, it is indicated that line 10 is to be changed. Line 10 is a statement which says that the employees will be exposed to vehicular traffic. The change to be made will state that it is unknown if the employees will be exposed to vehicular traffic. This change should

cause the value of SAFE to decrease, the value of UNSAFE to increase, and a text note to be added to the results. Screen 41 redisplays the question, and a new answer is given. This will return the system screen 40. Typing <R> will run the new data and yield screen 42.

As may be quickly noted, the results have changed from SAFE 10, UNSAFE 0, to SAFE 7, UNSAFE 3. This indicates an unsafe condition has been detected. Line 19 on Screen 44 informs the user of the problem. The procedure for tracing the rules which identified the problem is begun by typing the number 2, the line number of UNSAFE, at the bottom of Screen 44.

The system redisplays the final level of rules used to perform the analysis. Screen 45, 46, and 47 display these rules. The highlighting of Screen 47 informs the user that an improper accounting of all miscellaneous safety features has occurred. At this point, typing the number 1 will give the derivation of that condition.

By typing ENTER, one reaches Screens 49 and 50. To find out which miscellaneous safety feature was neglected, type in any line number from 1 to 10. A careful review of Screens 51 to 58 shows rules which fired to validate all the conditions of Screen 49 except line number 9, employee exposure to vehicular traffic.

By continuing to press enter, Screens 59 to 64 are displayed, each giving a new rule which was essential to the safety analysis. Had the missing item not been found, each

of these rules would need to be searched as shown in Screen 49.

Tracing rules in this manner is difficult and confusing. It is easy to get "nested" in 5 or 6 levels of explanation and rule displays. One can _always_ return to the results display by repeatedly pressing the RETURN key. Most often, the cause of an UNSAFE rating is listed along with the results. Rule tracing is not necessary unless there is some problem or question which the results listing does not answer. Competent rule tracing can only be achieved through experience. It is, however, highly educational to attempt it.

```
:MMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM:
:                                               :
:               E  X  S  Y  S                   :
:                                               :
:         Expert System Runtime Program         :
:                                               :
:                                               :
:         (c) copyright 1983.84.85 EXSYS, Inc.  :
:                                               :
:                                               :
:                                               :
:                 Ver. 3.1.9                    :
:                                               :
HMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM<
```

Press any key to start:

Screen 1

Do you wish instruction on running the program? (Y/N):

Screen 2

Do you wish to have the rules displayed as
they are used? (Y/N) (Default=N):

Screen 3

```
IMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM;
;                                                  ;
;           SAFETY ANALYSIS OF TRENCHES            ;
;                                                  ;
HMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM
```

by: Thomas C. Nicholas, LT,CEC.USN

                    Press any key to start:

                              .

                         Screen 4

SFTYCHEF is a prototype production system developed by T.C. Nicholas in partial fulfillment of the requirements for a Master of Engineering Degree in Civil Engineering, Construction Management at The Pennsylvania State University. This system is designed to assist in the safety analysis of light commercial trenching operations. It requires input on the soil conditions of the trenching site, although the only exact measurements required are to be done with a pocket penetrometer. No laboratory analysis is needed. The system also requires input on the trench itself, i.e. depth, width, etc. All other required input can easily be acquired without any research on your part.

For the most accurate results, run SFTYCHEF before opening the trench and answer all questions that can be answered. Then, store the data and rerun SFTYCHEF after opening the trench. Don't forget to recall the stored data.

When the analysis is complete, SFTYCHEF will give your operation a rating of safe or unsafe and will provide you with a proper shoring system design, the sloping criteria that must be met, any miscellaneous safety features that may be needed, and the effect of any unusual site construction methods.

Press any key to start:

Screen 5

106

The depth of the trench is
    1   0-5 feet
    2   5-10 feet
    3   10-15 feet
    4   15-20 feet
    5   20+ feet
    6   Unknown.

○ ←

Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 6

Investigation of the trench walls and floor reveals
   1   layered soil, with the slope of the layers dipping toward the trench
   2   layered soil, with the slope of the layers dipping away from the
        trench
   3   layered soil, with the slope of the layers not known
   4   homogeneous soil
   5   unknown
④ ←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 7

The primary composition of the excavated soils is
    1   fractured rock
    2   gravel
    3   sand
    4   silt (very fine sand)
    5   cohesive (clay-like) soil

⊙←

Screen 8

Please input the unconfined compressive strength of the soil in the wall of the
trench measured with a pocket penetrometer in tons per square foot (tsf)
: WHY

,DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Input a value for the variable between 0.000000 and 10.000000
WHY for information, or 'QUIT' to save data:

Screen 9

110

RULE NUMBER: 75
IF:

          (1)   the ultimate composition of the excavated soils is cohesive
                (clay-like) soil
and   (2)   [PENETROMETER] < 0.5

THEN:

                Investigation of the trench walls and excavated soils reveals
          soft soils

NOTE: Soft Soils are cohesive soils with an unconfined compressive
          strength (pocket penetrometer reading) of 0.5 tsf or less and granular
          soils that can not stand on a slope of 3 hor.: 1 vert. without slumping
          (much).

IF line # for derivation, <K>-known data, <C>-choices , <R>-reference,
 or   - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 10

111

RULE NUMBER: 45
IF:

    (1)   investigation of the trench walls and excavated soils reveals
            inclined layers dipping to the trench

THEN:

            the class of soil is type IV

IF line # for derivation, <K>-known data, <C>-choices
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 11

112

RULE NUMBER: 25
IF:

         (1)   The depth of the trench is 10-15 feet
and   (2)   The class of soil is type IV
and   (3)   [CLEARANCE] >= 30.0

THEN:

                    The safety analysis reveals sloping criteria which can be met

Screen 12

113

RULE NUMBER: 15
IF:

```
        (1)        The safety analysis reveals a shoring design which can be met
and     (2)        The safety analysis reveals sloping criteria which can be met
and     (3)        The safety analysis reveals an accounting of all miscellaneous
        safety features
and     (4)        The safety analysis reveals an evaluation of any unusual
        construction activities
```

THEN:

```
        SAFE - Probability=10/10
  and   UNSAFE - Probability=0/10
```

IF line # for derivation. <K>-known data. <C>-choices
or - prev. or next rule. <J>-jump. <H>-help or <ENTER> to continue:

Screen 13

114

Please input the unconfined compressive strength of the soil in the wall of the trench measured with a pocket penetrometer in tons per square foot (tsf)
: 1.30

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
nout a value for the variable between 0.000000 and 10.000000
WHY for information. or 'QUIT' to save data:

Screen 14

115

The undisturbed soil surrounding the trench can
    1   be easily penetrated several inches by your fist or it exudes between
         your fingers when squeezed in your hand
    2   be easily penetrated several inches by your thumb or molded by light
         finger pressure
    3   be penetrated several inches by your thumb with moderate effort or
         molded by strong finger pressure
    4   be readily indented by your thumb but penetrated only with great
         effort
    5   be readily indented by your thumb nail
    6   be indented with difficulty by your thumb nail

ᴰᴰᴰ
enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 15

116

The trench walls, or the trench floor is
    1   dry
    2   moist
    3   wet
    4   submerged or draining water

←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s), WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 16

Examination of the soil surface surrounding the excavation reveals
    1   cracks penetrating deeper than 25% of the trench depth (look at the
         trench wall)
    2   signs of previous disturbance (crossing underground utility lines are
         an example)
    3   vegetation that would suggest a fissured subsurface condition
    4   none of the above
④ ←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 17

118

The soil composing the trench walls is
    1   spalling of in chunks (chipping or flaking)
    2   not spalling

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered   or <H> for help

Screen 18

119

Please input the minimum, horizontal clearance, in feet, from the planned top edge of the trench to the nearest obstruction that might limit excavation : 4)

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Input a value for the variable greater than 0.000000
'WHY'for information. or 'QUIT' to save data:

Screen 19

120

The width of the trench is
1   0-3 feet
2   3-6 feet
3   6-9 feet
4   9-12 feet
5   12-15 feet
6   Unknown

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 20

121

Access into and out of the trench will be facilitated by the use of
    1   ramps
    2   ladders
    3   no ramps or ladders

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
enter number(s) of value(s), WHY for information on the rule.
QUIT to save data entered or <H> for help

                              1

                          Screen 21

                           122

There is some indication of
1   hazardous dusts
2   gases
3   fumes
4   mists
5   oxygen deficiencies
6   none of the above
7   unknown

1,5 →

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s), WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 22

123

Employees
    1   will be exposed to vehicular traffic
    2   will not be exposed to vehicular traffic
    3   unknown
○ ←——————

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s), WHY for information on the rule,
QUIT to save data entered or <H> for help

Screen 23

124

the construction site will contain or contains
1   supporting trenches
2   wells
3   pits
4   shafts
5   none of the above
6   unknown

‹—

Enter number(s) of value(s). WHY for information on the rule,
QUIT to save data entered, or ‹H› for help

Screen 24

The trench
    1   needs to be crossed over by men or equipment
    2   will not be crossed

① ←

ⅮⅮⅮ
Enter number(s) of value(s), WHY for information on the rule,
<H> to save data entered or <H> for help

Screen 25

126

The construction site contains
1   mobile equipment operating in the vicinity of the excavation (include
     excavators)
2   no mobile equipment
3   unknown

①←

ᵁᵁ
Enter number(s) of value(s), WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 26

The plans,specifications, or any other contract documents or field studies indicate

    1   sewer lines
    2   underground telephone lines
    3   water lines
    4   fuel lines
    5   electric lines
    6   no utilities whatsoever
    7   no available information on existing underground utilities

⊙ ←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 27

128

Preliminary investigation of the excavation site reveals
  1   trees
  2   boulders
  3   other surface encumbrances
  4   none of the above
  5   unknown, did not investigate

④ ←

᠌᠌᠌
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 28

129

The area around the trench will need
   1   walkways
   2   runways
   3   sidewalks
   4   none of the above
   5   unknown

④ ←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s), WHY for information on the rule,
QUIT to save data entered   or <H> for help

Screen 29

Examination of the soil surface before excavation reveals
    1   surface water
    2   no surface water

②←

Enter number(s) of value(s), WHY for information on the rule,
QUIT to save data entered or <H> for help

Screen 30

131

Construction operations on the site will require
    1   blasting
    2   no blasting
    3   unknown

②←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 31

```
Extreme dust conditions are
   1    anticipated
   2    not anticipated
   3    unknown
```
①←——

```
'DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
<I1 to save data entered  or <H> for help
```

Screen 32

133

Trench workers are likely to be exposed to
1   oxygen deficiency
2   flammable gas
3   none of the above
4   unknown

○ ←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 33

134

Crew personnel assignments include provisions for
    1   a safety inspector
    2   no safety inspector
    3   undecided

①←

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Enter number(s) of value(s). WHY for information on the rule.
QUIT to save data entered or <H> for help

Screen 34

the design of the shoring is to be done

    1   by a licensed engineer, because of particular concerns
    2   by experienced workmen in the field following Sftvchef's
         recommendations

○←

░░
Enter number(s) of value(s). WHY for information on the rule,
<Null> to save data entered or <H> for help

Screen 35

Please press any key to see the results of the safety analysis run. The results will each be assigned a number from 0 to 10. 10 meaning absolutely yes, and 0 meaning absolutely no. Because of the extreme importance of having an absolutely safe trenching operation, if the analysis results indicate unsafe or safe but the value is less than 10, retrace the rules used to arrive at this conclusion and find out why your trench is considered less than safe. Perhaps a minor adjustment in your procedures will save a life.

Press any key to display results:

Screen 36

137

```
        Values based on 0 - 10 system                          VALUE
1       SAFE                                                     10
2       The required minimum dimensions for the trench sheeting are = (2 X 6) OR
          (3 X 4)
3       The maximum sheeting center to center spacing  = CLOSE
4       The minimum dimensions of the wales = (4 X 6)
5       The maximum center to center wale spacing = 4 FEET
6       The minimum dimensions of the struts  = (6 X 8)
7       The maximum vertical center to center spacing of the struts  = 4 FEET
8       The maximum horizontal spacing of the struts = 6 FEET
9       The steepest allowable side-slope, Hor:Vert = (1 1/2 : 1)
10          The presence of mobile equipment in the vicinity of the excavation
        may require the use of stop logs or barricades.  In any case, the grade
        must be sloped away from the excavation.
11          Where employees or equipment are required or permitted to cross over
        excavations, walkways or bridges with standard guardrails shall be
        provided.
12          Personal protective equipment is required for the hands, eyes, head,
        feet, and lungs in all trenches and other protective equipment may be
        needed as conditions dictate.  Review OSHA 1926, Subpart E.
```

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD

Press any key for more:

Screen 37

13   Employees exposed to vehicular traffic shall be provided with and
shall be instructed to wear warning vests marked with or made of
reflectorized or high visibility material.

14   Conditions indicate the presence of hazardous dusts, gases, fumes,
mists, or an oxygen deficiency. Approved respiratory protection is
required. Consult OSHA 1926, Subpart D.

15   Daily inspections of excavations shall be made by a competent person.
If evidence of possible cave-ins or slides is apparent, all work in the
trench shall cease until the necessary precautions have been taken to
safeguard the employees. Excavations shall be inspected by a competent
person after every rainstorm or other hazard-increasing occurrence, and
the protection against slides and cave-ins shall be increased if
necessary.

16   Dust conditions shall be kept to a minimum by the use of water, salt,
calcium chloride, oil, or other means.

17   Excavated material shall be effectively stored and retained at least
2 feet or more from the edge of the excavation. The employer may use
effective barriers or othe effective retaining devices in lieu thereof
in order to prevent excavated or other materials from falling into the
excavation.

18   If the slope of the backfill behind the trench exceeds 3 Hor.: 1

∫∬∬

Press any key for more:

Screen 38

139

Next.. workers in this trench must be protected against objects rolling
or sliding from the sloped backfill. This can be accomplished by
projecting the sheeting at least 18" above the ground surface or by a
specially constructed protective sill.

Screen 39

140

```
1        The depth of the trench is 10-15 feet
2        The width of the trench is 6-9 feet
3        The design of the shoring is to be done  by experienced workmen in the
field following Sftychef's recommendations
4        Examination of the soil surface before excavation reveals no surface
water
5        The plans,specifications, or any other contract documents or field
studies indicate no utilities whatsoever
6        Preliminary investigation of the excavation site reveals none of the
above
7        The construction site contains mobile equipment operating in the
vicinity of the excavation (include excavators)
8        The construction site will contain or contains none of the above
9        The trench needs to be crossed over by men or equipment
(10)——— Employees will be exposed to vehicular traffic
11       There is some indication of hazardous dusts and fumes
12       The area around the trench will need none of the above
13        Crew personnel assignments include provisions for a safety inspector
14       Construction operations on the site will require no blasting
15       Extreme dust conditions are anticipated
16       Trench workers are likely to be exposed to none of the above

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDI
Enter number of line to change, <O> for original data, <R> to run the data.
<H> for help or any other key for MORE DATA: 10
```

***   The number 10 was entered because the input concerning the exposure
      of workmen to vehicular traffic will be changed. See page 99.

Screen 40

141

Employees
1   will be exposed to vehicular traffic
2   will not be exposed to vehicular traffic
3   unknown

```
DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
```
Enter number(s) of values. QUIT to save data entered or <H> for help

Screen 41

Values based on 0 - 10 system   VALUE PREV.

```
1    SAFE                                                    ──→{   7      10
2    UNSAFE                                                      {   3       0
3    The required minimum dimensions for the trench sheeting are = (2 X 6) OR
       (3 X 4)
4    The maximum sheeting center to center spacing  = CLOSE
5    The minimum dimensions of the wales = (4 X 6)
6    The maximum center to center wale spacing = 4 FEET
7    The minimum dimensions of the struts  = (6 X 8)
8    The maximum vertical center to center spacing of the struts  = 4 FEET
9    The maximum horizontal spacing of the struts = 6 FEET
10   The steepest allowable side-slope, Hor:Vert = (1 1/2 : 1)
11       The presence of mobile equipment in the vicinity of the excavation
     may require the use of stop logs or barricades.  In any case, the grade
     must be sloped away from the excavation.
12       Where employees or equipment are required or permitted to cross over
     excavations, walkways or bridges with standard guardrails shall be
     provided.
13       Personal protective equipment is required for the hands, eyes, head,
     feet, and lungs in all trenches and other protective equipment may be
```

ᗡᗡ

Press any key for more:

Screen 42

143

needed as conditions dictate.   Review OSHA 1926, Subpart E.

14   Conditions indicate the presence of hazardous dusts, gases, fumes, mists, or an oxygen deficiency.   Approved respiratory protection is required.   Consult OSHA 1926, Subpart D.

15   Daily inspections of excavations shall be made by a competent person. If evidence of possible cave-ins or slides is apparent, all work in the trench shall cease until the necessary precautions have been taken to safeguard the employees.   Excavations shall be inspected by a competent person after every rainstorm or other hazard-increasing occurrence, and the protection against slides and cave-ins shall be increased if necessary.

16   Dust conditions shall be kept to a minimum by the use of water, salt, calcium chloride, oil, or other means.

17   Excavated material shall be effectively stored and retained at least 2 feet or more from the edge of the excavation.   The employer may use effective barriers or othe effective retaining devices in lieu thereof in order to prevent excavated or other materials from falling into the excavation.

18   If the slope of the backfill behind the trench exceeds 3 Hor.: 1 Vert., workers in the trench must be protected against objects rolling or sliding from the sloped backfill.   This can be accomplished by

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Press any key for more:

Screen 43

projecting the sheeting at least 18" above the ground surface or by a
specially constructed protective sill.

19   A complete safety evaluation cannot be made unless you can tell me
whether or not employees will be exposed to traffic hazards.

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
all choices <A>, only if value>1 <G>, Print <P>, Change and rerun <C>,
rules used <line number>, Quit/save <Q>, Help <H>, Done <D>: 2

\

Screen 44

145

RULE NUMBER: 17
IF:

        (1)   The safety analysis reveals a shoring design which can be met

THEN:

                SAFE - Probability=9/10
  and   UNSAFE - Probability=1/10

ELSE:

                UNSAFE - Probability=9/10
  and   SAFE - Probability=1/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
#F line # for derivation. <K>-known data. <C>-choices
or - prev. or next rule. <J>-jump, <H>-help or <ENTER> to continue:

Screen 45

RULE NUMBER: 18
IF:

    (1)   The safety analysis reveals sloping criteria which can be met

THEN:

          SAFE - Probability=9/10
  and   UNSAFE - Probability=1/10

ELSE:

          SAFE - Probability=1/10
  and   UNSAFE - Probability=9/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
<F line # for derivation, <K>-known data, <C>-choices
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 46

147

RULE NUMBER: 19
IF:

    (1)   The safety analysis reveals an accounting of all miscellaneous
         safety features

THEN:

         SAFE - Probability=7/10
 and   UNSAFE - Probability=3/10

ELSE:

         SAFE - Probability=3/10
 and   UNSAFE - Probability=7/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
line # for derivation. <K>-known data. <C>-choices
or - prev. or next rule. <J>-jump. <H>-help or <ENTER> to continue: 1

Screen 47

RULE NUMBER: 26
IF:

        (1)   The depth of the trench is 10-15 feet
and   (2)   The class of soil is type III
and   (3)   [[CLEARANCE] >= 22.5

THEN:

           The safety analysis reveals sloping criteria which can be met

Screen 48

149

RULE NUMBER: 40
IF:

     (1)   An accounting of all miscellaneous safety features reveals
               consideration of location of underground utilities
and (2)   An accounting of all miscellaneous safety features reveals
               consideration of removal of surface encumbrances
and (3)   An accounting of all miscellaneous safety features reveals
               consideration of use of mobile equipment
and (4)   An accounting of all miscellaneous safety features reveals
               consideration of adequate barrier physical protection
and (5)   An accounting of all miscellaneous safety features reveals
               consideration of walkways and bridges
and (6)   An accounting of all miscellaneous safety features reveals
               consideration of ramps
and (7)   An accounting of all miscellaneous safety features reveals
               consideration of ladders
and (8)   An accounting of all miscellaneous safety features reveals
               consideration of personal protective equipment
and (9)——————— An accounting of all miscellaneous safety features reveals
               consideration of employees exposed to vehicular traffic
and (10)   An accounting of all miscellaneous safety features reveals
DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Press any key for more:

          consideration of special respiratory considerations

THEN:

          The safety analysis reveals an accounting of all miscellaneous
     safety features

ELSE:

          The safety analysis reveals a failure to account for all
     miscellaneous safety features

                         Screens 49 & 50

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
If line # for derivation. <K>-known data. <C>-choices . <R>-reference.
 or - prev. or next rule. <J>-jump. <H>-help or <ENTER> to continue:
                              150

RULE NUMBER: 56
IF:

      (1)   Access into and out of the trench will be facilitated by the use
              of no ramps or ladders

THEN:

              An accounting of all miscellaneous safety features reveals
              consideration of ramps
  and   An accounting of all miscellaneous safety features reveals
              consideration of ladders

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation, <K>-known data, <C>-choices
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 51

151

RULE NUMBER: 59
IF:

    (1)   The construction site will contain or contains none of the above

THEN:

        An accounting of all miscellaneous safety features reveals
       consideration of adequate barrier physical protection

Screen 52

152

RULE NUMBER: 62
IF:

    (1)   The plans,specifications, or any other contract documents or
            field studies indicate no utilities whatsoever

THEN:

          An accounting of all miscellaneous safety features reveals
      consideration of location of underground utilities

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation, <K>-known data, <C>-choices , <R>-reference,
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 53

153

RULE NUMBER: 61
IF:

    (1)   There is some indication of hazardous dusts or gases or fumes or
    mists or oxygen deficiencies

THEN:

        Conditions indicate the presence of hazardous dusts. gases.
    fumes. mists. or an oxygen deficiency. Approved respiratory
    protection is required. Consult OSHA 1926. Subpart D.
and   An accounting of all miscellaneous safety features reveals
    consideration or special respiratory considerations

Screen 54

154

RULE NUMBER: 65
IF:

    (1)   The depth of the trench is 0-5 feet or 5-10 feet or 10-15 feet
            or 15-20 feet or 20+ feet or Unknown

THEN:

            Personal protective equipment is required for the hands,
    eyes, head, feet, and lungs in all trenches and other protective
    equipment may be needed as conditions dictate.   Review OSHA 1926,
    Subpart E.
    and   An accounting of all miscellaneous safety features reveals
    consideration of personal protective equipment

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
line # for derivation, <K>-known data, <C>-choices , <R>-reference,
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 55

RULE NUMBER: 68
IF:

    (1)   The trench needs to be crossed over by men or equipment

THEN:

            Where employees or equipment are required or permitted to
    cross over excavations, walkways or bridges with standard
    guardrails shall be provided.
 and   An accounting of all miscellaneous safety features reveals
    consideration of walkways and bridges

Screen 56

156

RULE NUMBER: 70
IF:

    (1:   The construction site contains mobile equipment operating in the
             vicinity of the excavation (include excavators)

THEN:

             The presence of mobile equipment in the vicinity of the
        excavation may require the use of stop logs or barricades. In any
        case, the grade must be sloped away from the excavation.
    and   An accounting of all miscellaneous safety features reveals
        consideration of use of mobile equipment

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
F line # for derivation. <K>-known data. <C>-choices . <R>-reference.
or   - prev. or next rule. <J>-jump, <H>-help or <ENTER> to continue:

Screen 57

RULE NUMBER: 71
IF:

    (1)   Preliminary investigation of the excavation site reveals trees
           or boulders or other surface encumbrances

THEN:

          All surface encumbrances must be removed or made safe before
      excavation commences.
 and   An accounting of all miscellaneous safety features reveals
      consideration of removal of surface encumbrances

ELSE:

          An accounting of all miscellaneous safety features reveals
      consideration of removal of surface encumbrances

                  .

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation, <K>-known data, <C>-choices , <R>-reference,
or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue: 1

Screen 58

158

RULE NUMBER: 41
IF:

        (1)   An accounting of all hazardous construction site activities
                reveals a proper consideration of excavated materials
and   (2)   An accounting of all hazardous construction site activities
                reveals a proper consideration of walkways, runways, and sidewalks
and   (3)   An accounting of all hazardous construction site activities
                reveals a proper consideration of inspection procedures
and   (4)   An accounting of all hazardous construction site activities
                reveals a proper consideration of surface water removal
and   (5)   An accounting of all hazardous construction site activities
                reveals a proper consideration of blasting
and   (6)   An accounting of all hazardous construction site activities
                reveals a proper consideration of dust conditions
and   (7)   An accounting of all hazardous construction site activities
                reveals a proper consideration of adverse atmospheric conditions

THEN:

                The safety analysis reveals an evaluation of any unusual

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Press any key for more:

Screen 59

159

construction activities

ELSE:

            The safety analysis reveals an incomplete evaluation of any
        unusual construction activities

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation. <K>-known data, <C>-choices
or - prev. or next rule. <J>-jump, <H>-help or <ENTER> to continue:

                                 Screen 60

                                   160

RULE NUMBER: 43
IF:

         (1)   The depth of the trench is 0-5 feet or 5-10 feet or 10-15 feet
              or 15-20 feet
and   (2)   The class of soil is type I or type II or type III or type IV
and   (3)   The width of the trench is 0-3 feet or 3-6 feet or 6-9 feet or
              9-12 feet or 12-15 feet

THEN:

              The safety analysis reveals a shoring design which can be met

ELSE:

              Due to missing information, SFTYCHEF is not able to make a
         proper safety analysis of the trench shoring requirements. Please
         check the plans for trench depth and width and attempt to answer
         all questions relating to the soil characteristics so that a
         shoring recommendation can be made.

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation, <K>-known data, <C>-choices
 or - prev. or next rule, <J>-jump, <H>-help or <ENTER> to continue:

Screen 61

161

RULE NUMBER: 19
IF:

     (1)   The safety analysis reveals an accounting of all miscellaneous
         safety features

THEN:

         SAFE - Probability=7/10
  and   UNSAFE - Probability=3/10

ELSE:

         SAFE - Probability=3/10
  and   UNSAFE - Probability=7/10

Screen 62

162

RULE NUMBER: 20
IF:

    (1)   The safety analysis reveals an evaluation of any unusual
               construction activities

THEN:

               SAFE - Probability=7/10
    and   UNSAFE - Probability=3/10

ELSE:

               SAFE - Probability=3/10
    and   UNSAFE - Probability=7/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
IF line # for derivation. <K>-known data. <C>-choices
or - prev. or next rule. <J>-jump. <H>-help or <ENTER> to continue:

Screen 63

163

Values based on 0 - 10 system   VALUE PREV.

1   SAFE   7   10
2   UNSAFE   3   0
3   The required minimum dimensions for the trench sheeting are = (2 X 6) OR
       (3 X 4)
4   The maximum sheeting center to center spacing = CLOSE
5   The minimum dimensions of the wales = (4 X 6)
6   The maximum center to center wale spacing = 4 FEET
7   The minimum dimensions of the struts = (6 X 8)
8   The maximum vertical center to center spacing of the struts = 4 FEET
9   The maximum horizontal spacing of the struts = 6 FEET
10   The steepest allowable side-slope. Hor:Vert = (1 1/2 : 1)
11   The presence of mobile equipment in the vicinity of the excavation
       may require the use of stop logs or barricades. In any case, the grade
       must be sloped away from the excavation.
12   Where employees or equipment are required or permitted to cross over
       excavations, walkways or bridges with standard guardrails shall be
       provided.
13   Personal protective equipment is required for the hands, eyes, head,
       feet, and lungs in all trenches and other protective equipment may be

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
Press any key for more:

Screen 64

164

Summary

This chapter reviewed the fundamental objective of
SFTYCHEF. It then presented the four key safety aspects of
the trench operation which would be evaluated. A brief
discussion of SFTYCHEF's evaluative procedures and knowledge
base preceded comments concerning the optimum conditions for
use of the system. In order to acquaint the novice with the
details of system utilization, a short scenario was presented
and a "screen by screen" tutorial run of the system was
provided.

CHAPTER 6

CONCLUSIONS AND RECOMMENDATIONS

Summary

Problem Domain

Trench cave-ins are a serious problem in construction today and their elimination can only be facilitated by increased awareness and improved techniques of safety analysis. The light commercial contractor faced with excavating a short term trench has a variety of problems to consider while being bound by time and financial constraints. The contractor's main objective is satisfactory stabilization of the trench walls. The soil must be analyzed, the appropriate sloping angles must be investigated, and an adequate timber shoring system must be designed. Safety encompasses far more than trench wall stabilization, however, so the contractor must review the safety equipment to be supplied to the personnel and the jobsite as well as the potential hazards in the trench resulting from the surrounding construction.

Suitability for Expert Systems

The problem is very well suited to solution via expert systems. There are experts in the field of trench safety and

their expertise is widespread. It is certain that jobsites which have received expert attention are on the whole safer than those that have been neglected. A proper safety analysis is not lengthy with the exception of the soil analysis and the design of a shoring system. Using the Matrix Classification System and tables, however, the entire problem can be solved in a matter of hours. Anyone who has worked in a trench is well aware that the problem is ill-structured. Every site has different conditions and obstacles. These varied conditions coupled with time constraints, financial constraints, and the non-availability of technical expertise, often lead to safety analyses based upon the subjective knowledge of the workers on the site. The rewards of a safe trench are perhaps not obvious, but the consequences of an unsafe trench are known to all.

Construction of SFTYCHEF

SFTYCHEF is a production system built using EXSYS, an expert system shell, to assist the contractor faced with this problem. The system takes input from the contractor concerning trench parameters, soil conditions, and jobsite characteristics, performs a safety analysis, and outputs a statement concerning the degree of safety, a recommended timber shoring design, an allowable slope angle, and a listing of safety procedures and equipment required on the job.

SFTYCHEF utilizes backward chaining to derive

inferences. It has the ability to answer questions about its reasoning both during and after a consultation session. Confidence factors have been employed to provide the user with a degree of certainty in the analysis. The system will provide an analysis and recommendations based on worst case default values, if user input be incomplete. The simplicity of a pure production system allows modification of the knowledge base at any time through the addition of new rules or the deletion of existing rules. Rule ordering need not be considered.

SFTYCHEF

Current Stage of Development

SFTYCHEF is a functioning prototype which is currently capable of carrying out the above analysis. In its present condition, the system forms the foundation for a fully developed expert system.

Needed Work

The principal work remaining involves validation of the knowledge base through extensive expert interaction. It is certain that such interaction would expand and modify the rule base. The system must then be subjected to an intensive period of testing. SFTYCHEF should be distributed to a number of contractors in an observable field environment. The conclusions and recommendations of SFTYCHEF should then

be compared to those of the contractor's experts.

There are particular areas of the knowledge base which would benefit from further work. Although OSHA 1926 Table P-2 is currently the legal standard, it is very difficult to support the recommended designs with engineering calculations. The pressure calculations resulting from soil classification using the Matrix System can and have been used to develop similar tables (58). Work needs to be done in the area of verification of these tables so that they might replace Table P-2 in SFTYCHEF. Many engineers question the validity of tabular designed shoring systems due to the overabundance of site particular variables. A substantial addition to SFTYCHEF would be a link to a computational program which does the actual design of the shoring system. A simple beam supported on springs might provide an interesting model of analysis.

SFTYCHEF would benefit from the addition of alternate modes of trench wall stabilization. Trench jacks, hydraulic shores, and trench boxes all receive considerable field use. Their addition to SFTYCHEF would provide added flexibility to the contractor.

SFTYCHEF currently lists vital safety equipment and reference sources containing the details of the use or assembling of such equipment. SFTYCHEF could be expanded by providing a database of one page textual explanations covering the material from each reference. This would allow the user to get more elaborate answers to some of his

questions.

SFTYCHEF currently contains no information on lumber. Should the system be expanded to incorporate design capabilities, extensive data on lumber properties would have to be included in the system.

Modification

As has been mentioned several times throughout this report, the unimportance of rule ordering makes the addition of new knowledge to SFTYCHEF relatively simple. The bulk of the effort lies in knowledge acquisition and representation. As the system grows in content, it may become necessary to modularize the rules to increase readability, reduce run time, and eliminate excessive user interaction. EXSYS will not easily facilitate modularity. It is not possible to set pointers to a group of rules or to call a rule from another rule. As the system grows in size and content and modularity becomes a necessity, it may be necessary to leave the shell environment and program the system in Prolog or Lisp for mainframe or PC application.

AREAS FOR FUTURE RESEARCH

The use of expert systems in Civil Engineering is relatively new and the areas for future research are extensive. This research effort has uncovered several gaps in the field which must be promptly addressed

One gap is in the area of expert knowledge acquisition. There is very little information available which details the process of interacting with an expert to acquire knowledge. This lack of information stems from the fact that the primary researchers in expert systems have either been experts in the application of artificial intelligence techniques or domain experts researching the applicability of expert systems to their domain. The work produced tends to concentrate to a great extent on the construction of knowledge bases and their implementation. Interaction with an expert to elicit knowledge which will be the foundation of the system is very difficult and the process is as yet, vague. A compilation of techniques used would be very helpful.

A second gap is the selection and implementation of a knowledge representation scheme. Most papers concerning the design of an expert system describe the knowledge representation scheme utilized. Very seldom does one see a detailed account of how the scheme was selected and how the designer physically fit the knowledge into the scheme. Again, such information would be beneficial.

Another area of future research stems from the capabilities of EXSYS. EXSYS can be interfaced with spreadsheet programs such as LOTUS 1,2,3. This enables construction of a system which utilizes the powerful database features of the spreadsheet and the expert system abilities of the shell. Applications in this area are extensive.

EXSYS

The intent of this section is to provide evaluative comments on EXSYS, the expert system shell utilized. To users of EXSYS, it will provide little in the way of enlightenment. To the beginner, it will provide interesting reading but will be of little value. This section is primarily intended for users who are familiar with PC based shells and are looking for evaluative comments on the less visible features of EXSYS before use or purchase.

Strengths

Forward or Backward Chaining. The newest version of EXSYS can be utilized in either the forward or backward chaining mode. This nearly doubles the set of problems for which EXSYS is suited. It also allows the designer to fit the shell to the natural configuration of the problem instead of forcing the problem into the constraints of the shell.

Multiple Modes of Certainty and Probability Combination. As was mentioned earlier, EXSYS allows the use of certainty factors in one of three modes: yes/no, 0-10, and -100 - +100. It also allows the designer to select the method of combining certainty factors in the -100 - +100 mode. Certainty factors are either averaged, combined as dependent probabilities, or combined as independent probabilities.

Automatic Rule Checker. EXSYS has a built-in consistency enforcer which can either be switched on or off during editing. The checker alerts the designer when a rule has been entered which conflicts with another rule. This alert saves valuable time and effort during early developmental runs of the system.

Merging Two Distinct Rule Bases. EXSYS will allow two independent rule bases to be merged into one rule base using the utility disk. This is a very beneficial feature for large projects where parts of the system are designed separately and tested before being submitted as part of the larger system. It allows various team members to create independent rule bases and provides quick merging of the parts.

Interfacing with LOTUS 1,2,3. PC users familiar with spreadsheets can easily see the potential of such an interfacing capability. EXSYS can be used to run and control single and multiple spreadsheet programs. The tremendous data manipulation capabilities of LOTUS 1,2,3 and the simple, yet powerful heuristic decisiveness of EXSYS open an unlimited realm of applications.

Rule/Memory Capacity. EXSYS can create approximately 700 rules on a system with only 192K of RAM. For each additional 64K of RAM, EXSYS can create an additional 700 rules. This means that a system with 640K can accommodate nearly 5000 rules. 5000 well written rules can define a very extensive problem.

173

Shrink/Faster. The EXSYS utility disk contains two subroutines, **Shrink** and **Faster** which allow the designer to greatly reduce the run time of his completed system. Shrink removes all excess storage from the rule base and Faster rearranges the rules so that EXSYS can process them in the quickest fashion.

Simplicity of Use. EXSYS is a very user-friendly package. The three demonstration disks and the user's manual provide concise, explicit guidance. The designer need not be familiar with any programming language. All commands are issued in simple English. The on-line help facility and menu-style command options facilitate quick ease of use.

Weaknesses

Interacting with External Programs. EXSYS does have the ability to pass multiple bits of data to an external program. It can also pass a variable to an external program and receive a value for that variable. It cannot, however, make multiple calls and receive multiple feedback within one rule. Thus, a rule which requires two or more pieces of data held in another file cannot call for both pieces of information unless it can somehow be requested using one variable.

Inability to Utilize Certainty Factors Below First Level. EXSYS only tolerates the use of certainty factors within those rules whose consequents are goal nodes. All rules which do not directly evaluate a goal cannot utilize

the selected certainty factor mode. This does not mean that certainty factors cannot be utilized at deeper levels, it only means that the system designer must devise his own scheme of assigning certainty factors to common variables and passing them to other levels to be combined or eliminated. This requires that the designer be very familiar with certainty factors and their propagation.

Inability to Call a Rule From a Rule. Those familiar with MYCIN (50) are aware of the benefits of modularity in an expert system. A rule which selects only a certain block of rules to be evaluated can greatly decrease run time, user interaction, and useless data, and enhance readability. EXSYS rules cannot be written to call other rules by number so modularity is lost. This is a disadvantage of the pure production system.

Overwhelming Explanatory Data. As was mentioned in the section on SFTYCHEF's explanatory capabilities, EXSYS often provides an overabundance of rule listings when the user queries the derivation of a particular rule's antecedent. For users who are familiar with such systems or with computers in general, this excess information is at worst a nuisance. For users in construction who are possibly reluctant to use computers, such excess information could create enough confusion to cause the system to be abandoned.

Potentials of Joint Research

As this research effort progressed, the author became increasingly aware of the necessity to follow two independent tracks of research. Extensive work was done in the domain of trench safety. Due to a lack of prior background, a greater amount of work was used to develop the skills needed to create an expert system. During the research, the author encountered many students from other departments whose research thrust was in the particular aspects of expert system development. Their domains of application were somewhat irrelevant. Instead of burdening graduate civil engineers with advanced computer design skills and severely restricting the time needed to research some aspect of construction, it might be worthwhile to attempt joint research. A member of the construction field could serve as the domain researcher and assistant knowledge engineer for another student, perhaps an industrial engineer or a computer science major, who already has some expertise in the realm of expert systems. The construction student does not need to know the intricacies of system design if his goal is to apply a new technology. By working with another student, the construction student would become well versed in expert system technology and its applications, and the knowledge base researched could be quite substantial. The result could bring benefits to both departments.

REFERENCES

1.   "Artificial Intelligence." ENR, 20 March 1985, pp. 20-23.

2.   Barr, A. and Feigenbaum, E. A. The Handbook of Artificial Intelligence, Vol.2. Stanford, Ca.: Heuristic Press, 1982.

3.   Bennett, J. S., and Englemore, R. S. "SACON: A Knowledge-Based Consultant for Structural Analysis." Preceedings of the Sixth International Joint Conference on Artificial Intelligence. August 1979, pp. 47-49.

4.   Bennett, J. S., et al. "SACON: A Knowledge-Based Consultant for Structural Analysis." Technical Report 78-23, Stanford University Department of Computer Sciences, Heuristic Programming Project, September 1978.

5.   Buchanan, B. G., and Shortliffe, E. H. Rule-Based Expert Systems. New York, New York: Addison-Wesley, 1984.

6.   Buchanan, B. G.; Sutherland, G. L.; and Feigenbaum, E. A. "Heuristic DENDRAL: A Program for Generating Explanatory Hypothesis in Organic Chemistry." Machine Intelligence. Vol. 4, Edited by B. Meltzer and D. Michie. Edinburgh: Edinburgh University Press, 1969, pp. 209-254.

7.   Carson, Brinton A. General Excavation Methods. New York, New York: McGraw-Hill Book Co., 1961.

8.   Cass, W. Martin. Common Sense in the Common Trench. Palo Alto, Ca.: Equipment Guide-Book Company, 1979.

9.   Chang, T. C., Sanjay Joshi, R. L. Kashyap, S. R. T. Kumara, and C. L. Moodie, "Expert Systems in Industrial Engineering." Technical Report, Purdue University, W. Lafayette, IN, 1985.

10. Christiano, Paul P.; Konkoly, Gina Marie; and Rehak, Daniel R. A Shallow Trench Excavation Design Expert System. Technical Report R-86-155, Carnegie Mellon University, Pittsburgh, Pa., 1986.

11. Clocksin, W. F., and Mellish, C. S. Programming in Prolog. New York, New York: Springer-Verlag, 1984.

12. Cohen, P. R., and Feigenbaum, E. A. The Handbook of Artificial Intelligence, Vol. III. Los Altos, Ca.: William Kaufmann, Inc., 1982.

13. Date, C. J. An Introduction to Data Base Systems. Vol. 1. Reading, Massachusetts: Addison-Wesley Publishing Company, Inc., 1986.

14. Davis, R., and Lenat, D. Knowledge-Based Systems in Artificial Intelligence. New York, New York: McGraw-Hill, 1980.

15. Derfler, Frank J. "An Affordable Advisor." PC Magazine, Vol. 4, Number 8, 16 April 1985, pp. 113-117.

16. Derfler, Frank J. "Expert-Ease Makes Its Own Rules." PC Magazine, Vol. 4, Number 8, 16 April 1985, pp. 119-124.

17. Duda, R., and Gashing, J.G. "Knowledge-Based Expert Systems Come of Age." BYTE - A Small Systems Journal. Vol. 6, No. 9, September 1981, pp. 238-279.

18. Dunn, Irving S.; Anderson, Loren R.; and Kiefer, Fred W. Fundamentals of Geotechnical Analysis. New York, New York: John Wiley & Sons, Inc., 1980.

19. D'Ambrosio, B. "Expert Systems - Myth or Reality?" BYTE - A Small Systems Journal. January 1985, pp. 275-282.

20. EXSYS: Expert System Development Package. Version 3.1, EXSYS, Inc., Albuquerque, NM., 1983.

21. Feld, Jacob. Construction Failure. New York, New York: John Wiley & Sons, Inc., 1968.

22. Fenves, Steven J., and Rehak, Daniel R. "Expert Systems in Civil engineering, Construction Management, and Construction Robotics." Robotics Institute, Carnegie-Mellon University, Pittsburgh, PA, 1984.

23. Forgy, C. L. The OPS-5 User's Manual. Technical Report CMU-CS-81-135, Carnegie-Mellon University, Pittsburgh, Pa., 1981.

24. Fox, M. S. "The Intelligent Management System: An Overview," Technical Report CMU-RI-TR-81-4, IntelligentSystems Laboratory, The Robotics Instute, Carnegie-Mellon University, Pittsburgh, PA, 1983.

25. Goldenberg, Janet. "Experts on Call." PC WORLD, Vol. 3, Number 9, September, 1985, pp. 192-201.

26. Hayes-Roth, Frederick; Lenat, Douglas B; and Waterman, Donald A. eds. Building Expert Systems. 1st ed., Reading, Massachusetts: Addison-Wesley Publishing Company, Inc., 1983.

27. Hearn, L.; Lange, R.; and Kearney, F. "The Use of Knowledge Engineering Teams as a Method for the Development of Expert Systems." Unpublished Report by USA-CERL, November 1986.

28.   Hoadley, Anthony.   *Essentials of Structural Design*.   New York, New York: John Wiley & Sons, Inc., 1964.

29.   Ibbs, C. William, Jr.   "Proceedings of a Workshop for the Development of New Research Directions in Computerized Applications to Construction Engineering and Management Studies."   Construction Research Series No.   19, CEE 84-17681, National Science Foundation, The University of Illinois at Urbana-Champaign, 1985.

30.   *INSIGHT Knowledge System User's Guide*.   Version 1.2, Level 5 Research, Inc., Melbourne Beach, FL., 1983.

31.   Karna, Kamal N., ed.   *1985 Expert systems in Government Symposium*.   Washington, D.C.:   IEEE Computer Society Press, 1985.

32.   Kearney, F.; Preparata, P.; and Shaffer, R. "Artificial Intelligence for Construction and Maintenance Activities: The Critic Expert System."   Unpublished report by USA-CERL, November 1986.

33.   Kostem, Celal N., and Maher, Mary L., eds.   *Expert Systems in Civil Engineering*.   New York, New York: American Society of Civil Engineers, 1986.

34.   Lemley, Brad.   "Artificial Expertise: Intelligent Software for Problem Solving."   *PC Magazine*, Vol. 4, Number 8, 16 April 1985, pp. 108-112.

35.   Lisborg, Niels.   *Principles of Structural Design*. London, England: B.T. Batsford, Ltd., 1967.

36.   Marshall, Gilbert.   *Safety Engineering*.   Belmont, Ca.: Wadsworth Inc., 1982.

37.   Mason, George E., and Shimp, Steven C.   "Interpreting and Implementing OSHA Construction Trenching and Shoring Standards."   Unpublished Report, Ohio State University, 1974.

38.   McDermott, J.   *R1:   A Rule Based Configurer of Computer Systems*.   Technical Report CMU-CS-80-119, Carnegie-Mellon University, Pittsburgh, Pa., 1980.

39.   McGartland, M.R., and Hendrickson, C.T.   "Expert Systems for Construction Project Monitoring."   *Journal of Construction Engineering and Management*.   Vol. III, No.   3, September 1985, pp. 293-307.

40.   Michie, D. *Introductory Readings in Expert Systems*. Gordon and Breach Science Publishers, 1982.

41. Nillson, N.J., _Principles of Artificial Intelligence_.
Palo Alto, Ca.: Tioga Publishing Company, 1980.

42. Nunnally, S.W. _Construction Methods and Management_.
Englewood Cliffs, New Jersey: Prentice-Hall Inc., 1980.

43. Parker, Harry. _Simplified Design of Structural Wood_.
New York, New York: John Wiley & Sons, Inc., 1979.

44. Peck, Ralph B.; Hanson, Walter E.; and Thornburn, Thomas
H. _Foundation Engineering_. 2nd ed. New York, New York:
John Wiley & Sons, Inc., 1974.

45. _Personal Consultant Expert System Development Tools
User's Guide_. Version Revision A, Texas Instruments, 1985.

46. Peurifoy, R.L. _Formwork for Concrete Structures_. New
York, New York: McGraw-Hill Book Co., 1976.

47. Politakis, Peter G. _Empirical Analysis for Expert
Systems_. Boston, Massachussetts: Pitman Advanced Publishing
Program, 1985.

48. Rich, E. _Artificial Intelligence_. New York, New York:
McGraw-Hill, 1983.

49. Sell, P.S. _Expert Systems - A Practical Approach_. New
York, New York: Halstead Press, 1985.

50. Shortliffe, E. H. _Computer Based Medical Consultation:
MYCIN_. New York, New York: American Elsevier, 1976.

51. Simons, G. L. _Introducing Artificial Intelligence_.
Manchester, England: NCC Publications, 1984.

52. Tello, Ernie. "Raw Power for Problem Solving." _PC
Magazine_, Vol. 4, Number 8, 16 April 1985, pp. 131-137.

53. Tello, Ernie. "Marching to a Different Drummer." _PC
Magazine_, Vol. 4, Number 8, 16 April 1985, pp. 139-144.

54. Tello, Ernie. "The Languages of AI Research." _PC
Magazine_, Vol. 4, Number 8, 16 April 1985, pp. 173-189.

55. Ullman, J. D. _Principles of Database Systems_.
Rockville, MD: Computer Science Press, 1980.

56. U.S. Department of Commerce. National Bureau of
Standards. _BSS 121, Soil Classification for Construction
Practice in Shallow Trenching_. Washington, D.C.: Government
Printing Office, 1980.

57. U.S. Department of Commerce. National Bureau of Standards. BSS 122, A Study of Lumber Used for Bracing Trenches in the United States. Washington, D.C.: Government Printing Office, 1980.

58. U.S. Department of Commerce. National Bureau of Standards. BSS 127, Recommended Technical Provisions for Construction Practice in Shoring and Sloping of Trenches and Excavations. Washington, D.C.: Government Printing Office, 1980.

59. U.S. Department of Commerce. National Bureau of Standards. Development of Draft Construction Safety Standards for Excavations. Vol. I, Washington, D.C.: NBSIR 83-2693, 1982.

60. U.S. Department of Defense. Army Corps of Engineers. Safety and Health Requirements Manual. (EM 385-1-1). Washington, D.C.: Government Printing Office, 1981.

61. U.S. Department of Labor. Occupational Safety and Health Administration. OSHA Safety and Health Standards, Construction Industry (29 CFR 1926/1910). Washington, D.C.: Government Printing Office, 1979.

62. U.S. Department of Labor. Occupational Safety and Health Administration. Selected Occupational Fatalities Related to Trenching and Excavation as Found in Reports of OSHA Fatality/Catastrophe Investigations. Washington, D.C.: Government Printing Office, 1985.

63. Van Melle, W.; Shortliffe, E. H.; and Buchanan, B. G. "EMYCIN: A Domain Independent System That Aids in Constructing Knowledge Based Consultation Programs," Machine Intelligence, Infotech State of the Art Report 9, no. 3, pp. 281-287, 1981.

64. "Visionaries Meet Electronically to Confer on the Future of Computing." ENR, 30 May 1985, pp. 34-44.

65. Weiss, S. M., and Kulikowski, C. A. "Expert Consultation Systems: The EXPERT and CASNET Projects." Machine Intelligence, Infotech State of the Art Report 9, no. 3. 1981.

66. Winston, P. H. Artificial Intelligence. Reading, Ma.: Addison-Wesley Publishing Co., 1977.

67. Winston, P. H., and Horn, B. K. S. LISP. 2nd ed. Reading, Mass.: Addison Wesley Publishing Co., 1984.

68. Workshop on Principles of Knowledge-Based Systems. Silver Spring, MD: IEEE Computer Society Press, 1984.

APPENDIX I

EXPERT SYSTEMS AND THEIR APPLICATIONS

SYSTEM NAME	DOMAIN OF APPLICATION
1. AGE	Developing Expert Systems
2. AIRPLAN	Planning military air traffic movement
3. BUGGY	Identify students'basic arithmetic misconceptions
4. CADUCEUS	Diagnosis in internal medicine
5. CALLISTO	Modelling large manufacturing projects
6. CASNET	Diagnosis and therapy of glaucoma
7. CONGEN	Identify molecular structures
8. CRYSALIS	Protein crystallography
9. CUTTECH	Selects cutting tools, pass sizes, speeds and feeds that require machining expertise
10. DART	Diagnosis of computer system faults
11. DELTA	Troubleshoots diessel electrical locomotives
12. DENDRAL	Infers molecular structure from mass spectrographic data
13. DIPMETER ADVISOR	Analysis of oil well logging data
14. EMYCIN	General framework for expert systems
15. EXCAP	Generates process plans for machining of rotational components
16. EXCHECK	Logic and set theory tutor
17. FADES	Facilities planning and design system
18. GARI	Process planning
19. GENESIS	Planning gene splicing experiments
20. GPS	The general problem solver
21. GUIDON	Diagnostic problem solving
22. HEADMED	Psychopharmocologic advisor
23. HEARSAY-II	Speech understanding
24. HODGKINS	Kiagnostic planning for Hodgkins disease
25. HYDRO	Solving water resource problems
26. IFLAPS	Facilities layout analysis and planning system
27. IMACS	Aid manufacturing
28. IPMS	Aid project scheduling
29. ISA	Aid scheduling
30. ISIS	Production scheduling
31. ISIS-II	Scheduling of factory plant
32. KAS	Acquire knowledge for inspection
33. LDS	Making legal (product) decisions
34. LHASA	Laboratory synthesis
35. LUNAR	Answers questions for NASA
36. MACSYMA	Symbolic computation applied analysis
37. MATHLAB	Integration

MICROCOPY RESOLUTION TEST CHART

NATIONAL BUREAU OF STANDARDS 1963 A

38.	MYCIN	Consultative advice on diagnosis and therapy for infectious diseases
39.	ONCOCIN	Treatment of oncology out patients
40.	PIP	Kidney disease
41.	PROSPECTOR	Finding ore deposits from geological data
42.	PUFF	Pulmonary problems
43.	PWA-PLANNER	Prototype generative assembly planning package for printed wiring board assemblies
44.	QA3	Question and answering systems
45.	R1	Vax system configuration
46.	SACON	Assisting in structural engineering
47.	SAINT	Symbolic pattern matching
48.	SCHOLAR	Geography tutor
49.	SECOFOR	Advising on drilling
50.	SECS	Chemical analysis
51.	SIR	Question and answering system
52.	SIPP	Generative process planning of machined parts
53.	SOPHIE	Electronics laboratory instructor
54.	SPEAR	Analyzing computer error logs
55.	SPERIL	Structural damage assessment
56.	SYNCHEM	Laboratory synthesis of known substances
57.	TATR	Tactical air targeteering
58.	TEIRESIAS	Acquires, corrects, and uses knowledge for MYCIN
59.	TOM	Produces detailed machining plans
60.	VM	Intensive care monitor
61.	WAVES	Advise on seismic data analysis
62.	WEST	Guided discovery learning
63.	WHEAT COUNSELOR	Advising on the control of disease in winter wheat crops
63.	WHY	Tutors students in the causes of rainfall
64.	WUMPUS	Logic, probability, decision theory, and geometry
65.	XCON	Configuring and checking orders for VAX computers
66.	XPRES	Aids refining of organization procedures
67.	XSITE	Configuring and checking orders for VAX computers
68.	XSEL	Configuting and checking orders for VAX computers

APPENDIX II

EXPERT SYSTEM SHELLS: INFORMATIVE DATA FOR PURCHASE (25)

EXSYS

Exsys, Inc.
P.O. Box 75158, Contract Station 14
Albuquerque, NM 87194
(505)836-6674
List price: $395, demo disk $10, Runtime license $600
Requirements: for "small memory" version 128K, DOS 1.10
or 2.00; for "large memory" version 192K, DOS 2.00; one
disk drive (hard disk recommended).

Comments: Exsys allows up to 400 rules with 128K and
3000 rules with 640K. It is menu-driven and designed
for non-programmers; it tolerates uncertainty and can
explain why a decision was made.

EXPERT-EASE

Human Edge Software Corp.
2445 Faber Pl.
Palo Alto, CA 94303
(415)493-1593
Jeffrey Perrone and Assoc.
3685 17th Street
San Francisco, CA 94114
(415)431-9562
List price: $695
Requirements: 128K, one disk drive (hard disk
recommended).

Comments: Developed by Donald Michie, director of
Scotland's Turing Institute, Exper-Ease is an outgrowth
of Michie's quest to automate the knowledge-engineering
process. Unlike most other shells, Exper-Ease works by
induction, extracting rules from examples the system
builder enters. It is menu-driven and easy for
beginners to use but limited in application. (For
example, it does not allow certainty factors.) Expert-
Ease runs under the UCSD p-System and comes with a p-
System utility for tormatting data disks.

INSIGHT 2

Level Five Research Inc.
4980 S. Hwy. A1A
Melbourne Beach, FL 32951
(305)729-9046

List price: $495
Requirements: 128K (256K recommended), DOS 2.00, one
disk drive.

Comments: An expanded, upgraded version of Insight,
Insight 2 has a Pascal interface that can manipulate
data files in dBASE II. Both versions use a proprietary
language called PRL (Production Rule Language) to
formulate expert rules, which can then be applied
through simple menus. Maximum rule base in both
versions is 615 rules with 128K, 1800 rules with 256K,
with certainty factors allowed.

KDS

KDS Corp.
932 Hunter Road
Wilmette, IL 60091
(312)251-2621
List price: Development System $795, Playback Module
(for users of prefabricated applications) $495.
Requirments: playback mode 192K, development mode 256K,
DOS 2.00, two disk drives (hard disk recommended).

Comments: Written in assembly language, KDS allowa for
an exceptionally large rule base-up to 16,000 rules per
knowledge module. Menu-driven, it lets you enter rules
in comversational English and guides you through the
process of distinguishing on IF...THEN instance from
another. It performs forward or backward chaining and
can drive external programs in DOS.

KNOWLEDGE ENGINEERING SYSTEM

(KES)
Software Architecture and Engineering, Inc.
1500 Wilson Blvd. #800
Arlington, VA 22209
(703)276-7910
List price: $4000
Requirements: IBM PC XT or AT with 512K (640K
preferred) and 8087 math coprocessor.

Comments: This rule-based, backward-chaining program
can write knowledge bases that exceed available RAM,
thus supporting relatively large prototype systems. A
subset of the program, Micro-PS, is faster and can run
with 128K.

M.1

Teknowledge Inc.
525 University Ave.
Palo Alto, CA 94301
(415)327-6600
List price: $10,000, recommended training $2500, M.1a
$2000.
Requirements: 192K, DOS 2.00, two disk drives.

Comments: Oriented toward programmers, M.1 is among the
more powerful, flexible tools for creating small
applications. It typically forms a maximum of about 200
backward-chaing rules using a dBASE-like command
language. M.1 allowa certainty factors and can show how
decisions were made. Interface utilities can link M.1 to
external software or data bases or to information-
gathering deveces via an RS-232C port. M.1a, an
evaluation package for nonprogrammers, can be used to
create rudimentary applications.

MICRO-EXPERT

McGraw-Hill Book Co.
Professional and Reference Division
1221 Avenue of the Americas
New York, NY 10020
(212)512-2000
List price: $49.95
Requirements: 128K, DOS 2.00

Comments: Micro Expert uses rules, which can be written
with any standard word processor, to produce small,
functioning expert systems that will tolerate
uncertainty. A sample program included in the package
deduces tree species from leaf types.

PERSONAL CONSULTANT

Texas Instruments, Inc.
Data Systems Group
P.O. Box 809063
Dallas, TX 75380
(800)527-3500
List price: $3000, product training course $1500.
Requirements: 512K, DOS 2.10, 10MB hard disk.

Comments: This menu-driven development tool allows up
to 400 rules, created through question-and-answer
interaction. A built-in IQLISP module lets programmers
link a system to standard DOS business software.
Personal Consultant allows certainty factors and answers
queries about its reasoning.

RULEMASTER

Radian Corp.
8501 Mo-Pac Blvd.
P.O. Box 9948
Austin, TX 78766
(512)454-4797
List price: for PC or XT version $5000, for AT version $15,000.
Requirements: 256K; with PC XT, DOS 3.00 or PC/IX; with PC AT or compatible, DOS 3.00, PC/IX, or Xenix; with PC, two disk drives.

Comments: This menu-driven tool lets nonprogrammers create rules from examples; advanced user can write rules from.scratch using Radial, RuleMaster's proprietary development language. RuleMaster allows both backward- and forward-chaining inference. Systems will explain reasoning on demand and can handle uncertainty. RuleMaster accepts input from sensory devices, data bases, or any language running under UNIX-including FORTRAN, Pascal, C, LISP, or PROLOG.

TIMM-PC (The Intelligent Machine Model)

General Research Corp.
7655 Old Springhouse Rd.
McLean, VA 22102
(703)893-5915
List price: $9500 including training (additional licenses available at a discount).
Requirements: 640K, 10MB hard disk, 8087 math coprocessor (80287 math coprocessor with PC AT).

Comments: Originally designed for minicomputers and mainframes, TIMM-PC guides non-programmers through question-and-answer sessions that elicit examples and information. From these, TIMM-PC deduces rules that a developer can modify until the system works properly. TIMM-PC handles uncertainty and can define unfamiliar terms. It allows 90 rules per expert system in the primary knowledge base, and can link any number of expert systems together, provided that their cumulative knowledge base does not exceed 500 rules.

APPENDIX III

CORRESPONDENCE WITH DR. YOKEL

<div align="right">

The Pennsylvania State University
Department of Civil Engineering
212 Sackett Building
University Park, PA 16802

</div>

Mr. Felix Y. Yokel
U.S. Department of Commerce
National Bureau of Standards
National Engineering Laboratory
Center for Building Technology
Geotechnical Engineering Group
Structures Division
Washington, D.C. 20234

Dear Mr. Yokel:

My name is Tom Nicholas and I am a Lieutenant in the Navy's Civil Engineer Corps. Currently, I am doing graduate research at the Pennsylvania State University in Civil Engineering, Construction. The topic of my work is the development of a prototype Knowledge Base Expert System for Trench Safety Analysis. In essence, such a system is a micro-computer system which will ask questions of a contractor and then provide him with a soils analysis, shoring design, timber selection, and a list of safety features to comply with OSHA 1926 Subpart P.

A great deal of my system is based on a study you headed for NBS and the resultant publications:
1.) NBS BSS 121; Soil Classification for Construction Practice in Shallow Trenching
2.) NBS BSS 122; A Study of Lumber Used for Bracing Trenches in the United States
3.) NBS BSS 127; Recommended Technical Provisions for Construction Practice in Shoring and Sloping of Trenches and Excavations
4.) NBS/NIOSH; Development of Draft Construction Safety Standards for Excavations

The purpose of my writing is that I have encountered a problem which neither I nor any of the faculty here have been able to resolve. I was hoping you might spend some time reviewing the following pages and annotating any incorrect assumptions/calculations I have made so that I might continue on with my research.

The problem is in the calculation of bending stress, shear

stress, and deflection for timber members of a trench shoring system. The expert system currently prompts the user for information and does a soils analysis based on the MATRIX Classification System. It then assigns a lateral weight coefficient (We) to the soil class. Further prompting of the user allows the system to do a table look-up on either OSHA 1926 Table P-2 or NBS BSS 127 Table A.2/A.3 to get the recommended sheeting, wale, and strut dimensions and spacing. It then places this design structure against a soil wall with the given We and computes f(v), f(b), and E, so that a proper timber selection can be made. The problem is that the calculations all lead to stresses much greater than any common lumber can withstand.

The following pages of derivation and sample calculations should shed further light. Thank you so much for your prompt consideration.

Very respectfully,

Thomas C. Nicholas
LT, CEC, USN

Copy to:

Dr. J.H. Willenbrock

SUMMARY OF MY UNDERSTANDING OF YOUR DEVELOPMENT

OF (Wc)

$$P_{max} = \sigma_v = \gamma H$$

$$\sigma_H = K_a \sigma_v \quad ; \quad K_a = \frac{\sin^2(\alpha + \bar{\phi})}{\sin^2\alpha \, \sin(\alpha - \delta)\left[1 + \sqrt{\frac{\sin(\bar{\phi} + \delta)\sin(\phi - i)}{\sin(\alpha - \delta)\sin(\alpha + i)}}\right]}$$

$K_a \Rightarrow$ Based on Coulomb's analysis.

ASSUMED FAILURE SURFACES

Fundamentals of Geotechnical analysis by Dunn, Anderson, Kiefer p. 212.

FAILURE SURFACE

The calculation of $\bar{\phi}$, friction angle of the soil, requires a laboratory analysis and is generally not a practical item when the excavation is of short duration.

190

Peck, Hanson, and Thornburn recognized this and in their text Foundation Engineering, pages 424 and 425, they present empirical charts for estimating backfill pressure against a retaining wall based on slope angle i, and a coefficient K_V or K_H which has units of $\frac{lb}{ft^2}$ per lin. ft.

$$\frac{\text{FORCE}}{\substack{\text{UNIT LENGTH} \\ \text{OF TRENCH WALL}}} = \frac{1}{2}\left(K_a \gamma H\right)H = \frac{K_a \gamma H^2}{2} = \frac{1}{2} K_H H^2$$

$$\therefore \quad \left\{ K_H = K_a \gamma \right\}$$

It is my assumption that the lateral weight coefficient W_e which you have provided, is equivalent to Peck's K_H, for some average value of the slope angle.

If so, $K_H = W_e$ and $\frac{F}{\ell} = \frac{1}{2} W_e H^2$

Accounting for Non-homogeneous soils,

$$\frac{F}{\ell} \cong W_e H^2 \quad \Big\} \text{ i.e. a square pressure diagram}$$

Accounting for surcharge

$$\frac{F}{\ell} = W_e H (H+2)$$

$\therefore$ Pressure against the open face of the trench

$$P = \frac{F}{\ell(H)} = W_e (H+2) \frac{lb}{ft^2}$$

191

Summary of Structural Equations

Used for Timber Selection

Uniform Distributed Load
$\omega \ (lb/ft)$

Support conditions are assumed to be single span because this assumption provides maximum bend, shear, and deflection, and a contractor might use this support condition.

$$R_A = \frac{\omega l}{2} \qquad R_B = \frac{\omega l}{2}$$

$$V(x) = -\int \omega \, dx = -\omega x + c$$

$$V(0) = \frac{\omega l}{2} = c$$

$$V(x) = \frac{\omega l}{2} - \omega x$$

$$M(x) = \int V \, dx = \int \frac{\omega l}{2} - \omega x \, dx$$

$$M(x) = \frac{\omega l x}{2} - \frac{\omega x^2}{2} + C$$

$$M(0) = 0 = C$$

$$M(x) = \frac{\omega l x}{2} - \frac{\omega x^2}{2}$$

Maximum Moment

$$V = 0 \Rightarrow V\left(\frac{l}{2}\right)$$

$$M\left(\frac{l}{2}\right) = \frac{\omega l^2}{4} - \frac{\omega l^2}{8} = \frac{\omega l^2}{8}$$

Converting ω to $\frac{lb}{in}$, $\quad M\left(\frac{l}{2}\right) = \frac{\omega l^2}{8(.12)} = \frac{\omega l^2}{96} = \frac{\omega l^2}{6(16)}$

192

BENDING MOMENT CHECK

$$I = \frac{bd^3}{12}$$

BENDING STRESS, $f_b = \dfrac{Mc}{I}$

SECTION MODULUS, $S = \dfrac{I}{c} = \dfrac{I}{\left(\frac{d}{2}\right)} = \dfrac{bd^3}{12\left(\frac{d}{2}\right)} = \dfrac{bd^2}{6}$

$$f_b = \frac{M}{S} = \frac{6M}{bd^2}$$

$$M = \frac{w l^2}{6(16)} \quad \Big\}\ \text{from previous page}$$

$$\therefore \left\{ f_b = \frac{6 w l^2}{6(16)bd^2} = \frac{w l^2}{16 bd^2} \right\}$$

NOTE: This is more commonly seen in the form

$$\left\{ l = 4.0 d \left(\frac{f_b \, b}{w} \right)^{1/2} \right\}$$

HORIZONTAL SHEAR, F_v

For a rectangular member

$$F_v = \frac{f_v}{f_v} = \frac{3}{2}\frac{V}{bd} = \frac{3}{2}\frac{V}{A} \quad ; \quad V = \text{maximum vert. shear at support}$$

$$f_v = \frac{3}{2}\left(\frac{wl}{2}\right)\frac{1}{A} = \frac{3}{4}\frac{wl}{A} = \frac{3}{4A}wl \quad \left(w \text{ in } \frac{lb}{in.}\right)$$

For Lumber $l \Rightarrow l - 2d$

NOTE:
"Checks and shakes are present in nearly all structural lumber. Because of their presence, the upper and lower portions of a beam act partly as two beams and partly as a unit. The conservative results given by the formula for horizontal shearing stress are partly a consequence of this "two-beam" action. This fact has led to an <u>empirical</u> rule that permits the end shears (reactions) of a simple beam to be calculated by neglecting all loads within a distance equal to the depth of the beam from both supports."

<u>Simplified Design of Structural Wood</u>

by Harry Parker, John Wiley & Sons, © 1979

p 64

$$\therefore \left\{ f_v = \frac{3w}{4A}(l-2d) = \frac{wl}{16A}\left(1 - \frac{2d}{l}\right)\right\} **$$

This is more commonly seen as

$$\left\{ l = 16.0\frac{F_v A}{w} + 2d \right\}$$

** Same Eqn used in "National Design Specifications for Stress-Grade Lumber and Its Fastenings," 1973 ed, Section 300-E-1, NFPA.

194

DEFLECTION

For a simply supported beam with continuous loading

$$Defl. = \frac{5 w l^4}{4608 \, EI} \quad (in.)$$

Using: $\Delta = \dfrac{l}{360}$ as a conservative assumption

$$\frac{l}{360} = \frac{5 w l^4}{4608 \, EI}$$

$$l^3 = \frac{4608 \, EI}{5 w (360)} = 2.56 \frac{EI}{w}$$

$$\left\{ l = 1.37 \left(\frac{EI}{w} \right)^{1/3} \right\} \quad \text{Common form}$$

$$\text{or} \left\{ E = \frac{w l^3}{2.56 \, I} \right\}$$

SAMPLE CALCULATION I

<u>GIVEN</u> SOIL TYPE I $\Rightarrow$ W_e = 20 $\frac{lb}{ft^3}$

H = 5 – 10 ft ; use 10 ft.

TABLE A.2 (NBS BSS 127)

STRUTS, 4" × 4" @ 6'-0" O.C. HORIZ, 4'-0" O.C VERT

SHEETING, 2" × 6" @ 6'-0" O.C

WALES, NONE REQUIRED

<u>DETERMINE</u> f_b, f_v, and E, and select a timber to use for sheeting

<u>SOLUTION</u>

b = 5.5 in d = 1.5 in l = 48" (Unsupported length)

<u>BENDING</u>

$$f_b = \left(\frac{l}{4d}\right)^2 \frac{w}{b}$$

PRESSURE = $W_e(H+2)$ = 20 $\frac{lb}{ft^3}$ (12 ft) = 240 $\frac{lb}{ft^2}$

w = $\left(240 \frac{lb}{ft^2}\right)(6 ft)$ = 1440 $\frac{lb}{ft}$

Sheeting spacing

$$f_b = \left(\frac{48 in}{4(1.5 in)}\right)^2 \frac{1440 lb}{12 in/ft} \frac{1}{ft} \frac{1}{5.5 in} = 1396 \frac{lb}{in^2} = \boxed{1396 \; psi}$$

<u>SHEAR</u>

$$f_v = \left(\frac{L-2d}{16}\right)\frac{w}{6d}$$

$$= \left(\frac{48\,in - 2(1.5\,in)}{16}\right)\frac{1440\,lb}{12\frac{in}{ft}\,ft}\frac{1}{(5.5\,in)(1.5\,in)} = \boxed{40.41\,psi}$$

<u>Deflection</u>

$$E = \left(\frac{L}{1.37}\right)^3\left(\frac{12w}{6d^3}\right)$$

$$= \left(\frac{48\,in}{1.37}\right)^3\left(12\left(\frac{1440\,lb}{12\frac{in}{ft}\,ft}\right)\frac{1}{(5.5\,in)}\frac{1}{(1.5\,in)^2}\right)$$

$$\boxed{E = 3,336,476.2\,psi}$$

<u>TIMBER SELECTION</u>

Ref. NBS BSS 122   Table 4, p. 33

$$\left.\begin{array}{l} f_b = 1396\,psi \\[4pt] f_v = 40.91\,psi \\[4pt] E = 3,336,476.2\,ps. \end{array}\right\}$$ $\boxed{\text{There is no lumber which can withstand these pressures.}}$

<u>NOTE</u>   The problem becomes worse as different classes of soil, (i.e greater h':) are combined with deeper trenches. Because OSHA 1926 Subpart P is still the law, table P-2 is being used by my system for dimension and spacing requirements The problem is similar.

November 17, 1068

Lt. Thomas C. Nicholas
The Pennsylvania State University
Department of Civil Engineering
212 Sackett Building
University Park, PA 16802

Dear Mr. Nicholas:

I read your recent letter on your work on an expert system for
shoring with interest. Recently a graduate student in Carnegie-
-Mellon university worked on a similar project. You may want to
have a look at her work, presented in Technical Report R-86-
-155,"A Shallow Trench Excavation Design Expert System" by
G.N. Konkoly, D.R. Rehak, and Paul, P. Christiano.

You have to realize that we deal here with several issues:

1. If we develop a new shoring system, how should it be designed
in order to be reasonably adequate? For this case, our guidelines
which were developed so that construction foremen can use them
(ASFE told us in no uncertain terms that professional engineers
refuse to get invoved in bracing of shallow trenches), will give
you reasonable results which are acceptable from a safety
standpoint without being excessively overdesigned.

You should note, that after much discussions with the parties
invoved (contractors and labor unions) we settled for the
simplified classification and not for the matrix. The reason for
this is twofold: (1) formen could handle the simplified system
well, while the matrix turned out to be too comlex and required
too many decisions which they are not qualified to make. (2)
There is a strong preference, for reasons of efficiency, for
three force levels, each twice as high as the preceeding one (you
can swich by merely using intermediate struts (wales will be
O.K.)).

2. Are existing systems adequate? Here you are running into
problems with some timber system (not hydraulic shores or trench
boxes). The struts tend to check out, while the wales for larger
spans tend to be unsafe. You can explain why they do not fail
often. For instance few timber members will fail when subjected
to 1400 psi stress (the safety factor tends to exceed 2).One of
the reasons for the problem is that for larger spans contractors
frequently use cages, where they double the intermediate wales by
stacking two cages or more.

My own reaction to this problem is that many of these systems will go the way of the dynosaurs and they should be replaced by other systems which can be shown to be adequate. We could not in good face reduce the strength requirements just because some timber shorings cannot comply with them. Table P-2 may still be the law, but OSHA is revising their provisions and they probably will not keep this table.

As for your calculation, I have some comments. Your lateral pressure analysis on calculation page 1 is flawed, because the Coulomb equation applies to walls who can rotate at the top, and not to restrained (braced) walls. Look at Terzaghi's Theoretical Soil Mechnics and at some of Peck's papers I referenced. Your example of spaced sheeting for Class A (Type I) soil also does not apply. For these soils it is assumed that the shoring can be spaced because the soil will arch. Frequently the vertical members are omitted, and hydraulic shores resting on square plywood panels are used, spacing the support horizontally as well as vertically. The main function of the vertical member in this case is to spread the concentrated load applied by the strut. The member in this case would by more like a beam on an elastic foundation, which would generate a smaller moment at its center.

I hope that my discussion does not confuse you and I wish you luck with your project. Please do not hesitate to call if you have any further questions.

Sincerely

Felix Y. Yokel, Ph.D., P.E.
Seenior Research Civil Engineer
Structures Division
Bdg. 226, Rm. B162

SFTYCHEF RULES 015 - 020

RULE NUMBER: 19

IF:
(1)   The safety analysis reveals a shoring design which can be met
and (2)   The safety analysis reveals sloping criteria which can be met
and (3)   The safety analysis reveals an accounting of all miscellaneous
            safety features
and (4)   The safety analysis reveals an evaluation of any unusual
            construction activities

THEN:
(1)   SAFE - Probability=10/10
and (2)   UNSAFE - Probability=0/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
CHANGE: If <I>, Then <T>, Else <E>. Note <N>. Reference <R>. Done <ENTER>
for previous rule. for next rule:

RULE NUMBER: 16

IF:
     (1)   The safety analysis reveals a shoring design that can not be
          met
and (2)   The safety analysis reveals sloping criteria that can not be
          met
and (3)   The safety analysis reveals a failure to account for all
          miscellaneous safety features
and (4)   The safety analysis reveals an incomplete evaluation of any
          unusual construction activities

THEN:
     (1)   UNSAFE - Probability=10/10
and (2)   SAFE - Probability=0/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD
CHANGE: If <I>. Then <T>. Else <E>. Note <N>. Reference <R>. Done <ENTER>
 for previous rule. for next rule:

RULE NUMBER: 17

IF:
   (1)   The safety analysis reveals a shoring design which can be met

THEN:
   (1)   SAFE - Probability=9/10
and   (2)   UNSAFE - Probability=1/10

ELSE:
   (1)   UNSAFE - Probability=9/10
and   (2)   SAFE - Probability=1/10

RULE NUMBER: 18

IF:
    (1)   The safety analysis reveals sloping criteria which can be met

THEN:
    (1)   SAFE - Probability=9/10
and (2)   UNSAFE - Probability=1/10

ELSE:
    (1)   SAFE - Probability=1/10
and (2)   UNSAFE - Probability=9/10

.

RULE NUMBER: 19

IF:
    (1)   The safety analysis reveals an accounting of all miscellaneous
          safety features

THEN:
    (1)   SAFE - Probability=7/10
and (2)   UNSAFE - Probability=3/10

ELSE:
    (1)   SAFE - Probability=3/10
and (2)   UNSAFE - Probability=7/10

DDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDDD

CHANGE: If <I>. Then <T>. Else <E>. Note <N>. Reference <R>. Done <ENTER>
 for previous rule. for next rule:

204

RULE NUMBER: 201

If:
        (1)   The safety analysis reveals an evaluation of any unusual
                     construction activities

THEN:
        (1)   SAFE - Probability=7/10
and   (2)   UNSAFE - Probability=3/10

ELSE:
        (1)   SAFE - Probability=3/10
and   (2)   UNSAFE - Probability=7/10

EMD

6 - 87

DTIC